**APPENDIX 4B** 

### Interpretative Report for Infiltration System (Rancho Bonito)

#### **INTERPRETIVE REPORT**

FOR INFILTRATION SYSTEM DESIGN, PROPOSED RANCHO BONITO TOWN HOMES COMMUNITY AND SHOPPING CENTER, ASSESSOR'S PARCEL NUMBER 360-350-006, LOT NUMBER 1 OF PARCEL MAP NUMBER 13523, LOCATED ON THE SOUTH SIDE OF GARBANI ROAD BETWEEN SHERMAN ROAD AND HAUN ROAD, CITY OF MENIFEE, RIVERSIDE COUNTY, CALIFORNIA

PROJECT NO. 151015-12A

ISSUED: February 29, 2016

EARTH STRATA GEOTECHNICAL SERVICES, INC.

February 29, 2016

Project No. 151015-12A

SHERMAN & GARBANI. LLC 31103 Rancho Viejo Road San Juan Capistrano, CA 92675

- Subject: Interpretive Report for Infiltration System Design, Proposed Rancho Bonito Town Home Community and Shopping Center, Assessor's Parcel Number 360-350-006, Lot Number 1 of Parcel Map Number 13523, Located on the South Side of Garbani Road Between Sherman Road and Haun Road, City of Menifee, Riverside County, California
- Reference: Earth Strata Geotechnical Services, 2016, Preliminary Geotechnical Interpretive Report, Proposed Rancho Bonito Town Home Community and Shopping Center, Assessor's Parcel Number 360-350-006, Lot Number 1 of Parcel Map Number 13523, Located on the South Side of Garbani Road Between Sherman and Haun Road, City of Menifee, Riverside County, California, dated February 4.

Earth Strata Geotechnical Services is pleased to present this interpretive report for the proposed development, located on the south side of Garbani Road between Sherman Road and Haun Road in the City of Menifee in Riverside County, California. The purpose of our study was to determine the infiltration rates and physical characteristics of the subsurface earth materials within the proposed development. We have provided guidelines for the design of onsite bio swale retention systems, where applicable. This study is intended to provide onsite infiltration rates for the earth materials at the approximate depth of the proposed water quality retention areas located in the northeast corner of the subject property.

#### **PROPERTY DESCRIPTION**

The subject property is located on the south side of Garbani Road between Sherman Road and Haun Road in the City of Menifee in Riverside County, California (see Figure 1). The subject property consists of an undeveloped parcel of land with relatively flat terrain. The subject property is underlain by alluvium deposits.

#### **PROPOSED CONSTRUCTION**

Based on information provided by you, the proposed development will consist of one (1) to three (3) story, multifamily apartment buildings which include interior driveways, utilities and two on-site water quality management areas located along the northeast corner of the proposed development.

#### **SUBSURFACE EXPLORATION AND INFILTRATION TESTING**

#### SUBSURFACE EXPLORATION

Subsurface exploration of the subject site consisted of eight (8) exploratory excavations to a depth of 9 feet conducted on December 28, 2015 for the geotechnical study and five (5) infiltration tests performed on December 30, 2015. The exploratory holes were excavated to evaluate insitu soils. Infiltration tests were executed and tested

to evaluate insitu permeability rates. The approximate locations of the exploratory excavations and infiltration tests are shown on the attached Infiltration Location Map, Plate 1. The boring logs for the geotechnical study are included in the referenced report.

#### EARTH MATERIALS

A general description of the earth materials observed on site is provided below.

- <u>Quaternary Very Old Alluvial Channel Deposits (map symbol Qvoa)</u>: Quaternary very old alluvial deposits were encountered to the maximum explored depth. These alluvial deposits consist predominately of interlayered reddish brown to yellowish brown, fine to coarse grained silty sand. These deposits were generally noted to be in a slightly moist to moist, medium dense to very dense state.
- <u>Cretaceous Gabbro (map symbol Kgb)</u>: Cretaceous age plutonic rock consisting of gabbro was mapped within the western portion of the site. The gabbro was observed to be dark gray to olive gray, fine to coarse grained, and in a moderately hard to very hard state. Typically, the upper 1 to 3 feet of this unit is more weathered and not as hard.
- <u>Cretaceous Monzogranitic Rock (map symbol Kpvg)</u>: Cretaceous age monzogranitic rocks composed of a wide variety of compositions make up this unit. Rock types typically include monzogranite, granodiorite, tonalite and gabbro, with the most common being tonalite (Morton, 2004). This rock unit was mapped within the eastern portion of the site. These granitic rocks were observed to be yellowish brown to reddish brown, medium to coarse-grained, and in a moderately hard to very hard state. Typically, the upper 1 to 3 feet of this unit is more weathered and not as hard.

#### GROUNDWATER

Groundwater was not observed within the exploratory excavations.

#### INFILTRATION TESTING

The infiltration testing was performed per the Appendix A of the Riverside County Flood Control Water Conservation District, Best Management Practices. The testing performed followed the percolation testing requirements of the Riverside County Department of Environmental Health. The percolation rates were then converted per to infiltration rates utilizing the Porchet Method as per Appendix A of the Flood Control Manual.

TEST NUMBER	INFILTRATION HOLE DEPTH (ft.)	INFILTRATION RATE (inches/hour)	DESCRIPTION
P-1	5.5	0	Silty SAND
P-2	4.7	0.30	Silty SAND
P-3	4	0.62	Silty SAND
P-4	3	0.30	Silty SAND
P-5	3	0	Silty SAND

#### **INFILTRATION TEST SUMMARY**

The infiltration test rates ranged from 0 to .62 inches per hour.

#### **CONCLUSIONS AND RECOMMENDATIONS**

The following Porchet equation was used in order to convert the percolation rates to infiltration rates.

$$I_{t} = \frac{\Delta H (60) r}{\Delta t (r + 2Havg)}$$

Based on the data presented in this report and the recommendations set forth herein, it is the opinion of Earth Strata Geotechnical Services that the water quality management areas can be designed for an infiltration rate of 0.30 inches per hour.

See attached sheet for infiltration tests and field data.

#### **GRADING PLAN REVIEW AND CONSTRUCTION SERVICES**

This report has been prepared for the exclusive use of **SHERMAN & GARBANI** and their authorized representative. It likely does not contain sufficient information for other parties or other uses. Earth Strata Geotechnical Services should be engaged to review the final design plans and specifications prior to construction. This is to verify that the recommendations contained in this report have been properly incorporated into the project plans and specifications. Should Earth Strata Geotechnical Services not be accorded the opportunity to review the project plans and specifications, we are not responsibility for misinterpretation of our recommendations.

Earth Strata Geotechnical Services should be retained to provide observations during construction to validate this report. In order to allow for design changes in the event that the subsurface conditions differ from those anticipated prior to construction.

Earth Strata Geotechnical Services should review any changes in the project and modify and approve in writing the conclusions and recommendations of this report. This report and the drawings contained within are intended for design input purposes only and are not intended to act as construction drawings or specifications. In the event that conditions encountered during grading or construction operations appear to be different than those indicated in this report, this office should be notified immediately, as revisions may be required.

#### **REPORT LIMITATIONS**

Our services were performed using the degree of care and skill ordinarily exercised, under similar circumstances, by reputable soils engineers and geologists, practicing at the time and location this report was prepared. No other warranty, expressed or implied, is made as to the conclusions and professional advice included in this report.

Earth materials vary in type, strength, and other geotechnical properties between points of observation and exploration. Groundwater and moisture conditions can also vary due to natural processes or the works of man on this or adjacent properties. As a result, we do not and cannot have complete knowledge of the subsurface conditions beneath the subject property. No practical study can completely eliminate uncertainty with regard to the anticipated geotechnical conditions in connection with a subject property. The conclusions and recommendations within this report are based upon the findings at the points of observation and are subject to confirmation by Earth Strata Geotechnical Services during construction. This report is considered valid for a period of one year from the time the report was issued.

This report was prepared with the understanding that it is the responsibility of the owner or their representative, to ensure that the conclusions and recommendations contained herein are brought to the attention of the other project consultants and are incorporated into the plans and specifications. The owners' contractor should properly implement the conclusions and recommendations during grading and construction, and notify the owner if they consider any of the recommendations presented herein to be unsafe or unsuitable.

Respectfully submitted,

EARTH STRATA GEOTECHNICAL SERVICES

opten M. Vo

Stephen M. Poole, PE 40219 President Principal Engineer

SMP/mw/sw

Distribution: (2) Addressee

Attachments: Figure 1 – Vicinity Map *(Rear of Text)* Appendix A – Infiltration Test Sheets *(Rear of Text)* Plate 1 – Infiltration Location Map *(Rear of Text)* 



# **FIGURE 1** VICINITY MAP



## **APPENDIX A**

## **INFILTRATION TEST SHEETS**

ob No.:	151015-12	<u>2</u> A			Tested By:	RCG	
Job Name:	Rancho Bo	onito Town Home	es				
Test Hole I	Number:	P-1	Test H	lole Diamet	er (inches):	8	
Soil Classif	ication:	SM		Dat	e Excavated:	12/28/2015	
Test Hole I	Depth (ft):	5' 5"		I	Date Tested:	12/30/2015	
			Time Interva	al of Presoak			
Date / Time	9		0				
Start	12/30/1	<mark>5 11:11</mark>	Amount of V	Water Used	/ Comments		
Stop	12/30/1	<mark>5 17:11</mark>	0				
Time	Time Interval (min.)	Initial Water Level (Inches)	Final Water Level (Inches)	Water Level Drop (Inches)	Percolatio n Rate (Min./Inch )	Total Depth of Percolation Hole	
11:11	30	53	56	3.00	10	65.00	
11:41	30	51	53	2.00	15	63.00	
12:11	50			2.00	15		-
12:11	30	50	51	1.00	30	62.00	
12:41	30	50	51	1.00	30	62.00	
13:11	20	50	E 1	1.00	20	62.00	
13:41	50	50	51	1.00	50	02.00	
13:41	30	49	50	1.00	30	61.00	
14:11	30	49	49	0.00	-	61.00	
14:41	30	49	49	0.00	_	61.00	
15:11	50		43	0.00		01.00	_
15:41	30	49	49	0.00	-	61.00	
15:41 16:11	30	49	50	1.00	30	61.00	
16:11	30	49	49	0.00	-	61.00	
16:41	30	49	49	0.00	-	61.00	
17:11							-
							-
					4		<u> </u>

"It" is the tested infiltration rate. Time interval,  $\Delta t$  Initial Depth to Water, Do Final Depth to Water, Df Total Depth of Test Hole, DT 2Test Hole Radius, r The conversion equation is used: "Havg" is the average head height over the time interval.

 $It = \frac{\Delta H 60 r}{\Delta t (r+2 Havg)}$ 

Time interval ∆t	Initial Water H o	Final Water Hf	Total Depth of Test Hole D t	Raduis of Perc Hole r	ΔН	H Avg	ΔΗ 60 r)/(Δt (r+2Havg)) It	ELAPSED TIME Δt
30.00	12.00	9.00	65.00	4.00	3.00	10.50	0.96	30.00
30.00	12.00	10.00	63.00	4.00	2.00	11.00	0.62	60.00
30.00	12.00	11.00	62.00	4.00	1.00	11.50	0.30	90.00
30.00	12.00	11.00	62.00	4.00	1.00	11.50	0.30	120.00
30.00	12.00	11.00	62.00	4.00	1.00	11.50	0.30	150.00
30.00	12.00	11.00	61.00	4.00	1.00	11.50	0.30	180.00
30.00	12.00	12.00	61.00	4.00	0.00	12.00	0.00	210.00
30.00	12.00	12.00	61.00	4.00	0.00	12.00	0.00	240.00
30.00	12.00	12.00	61.00	4.00	0.00	12.00	0.00	270.00
30.00	12.00	11.00	61.00	4.00	1.00	11.50	0.30	300.00
30.00	12.00	12.00	61.00	4.00	0.00	12.00	0.00	330.00
30.00	12.00	12.00	61.00	4.00	0.00	12.00	0.00	360.00



ob No.:	151015-12	A			Tested By:	RCG
ob Name:	Rancho Bo	nito Town Home	es			
Test Hole I	Number:	P-2	Test H	8		
Soil Classif	ication:	SM		Date	e Excavated:	12/28/2015
Test Hole I	Depth (ft):	4' 8"		l.	Date Tested:	12/30/2015
		-	Time Interva	l of Presoak		
Date / Time	e		0			
Start	12/30/1	<mark>5 11:12</mark>	Amount of \	Water Used	/ Comments	
Stop	12/30/1	5 17:12	0			
Time	Time Interval (min.)	Initial Water Level (Inches)	Final Water Level (Inches)	Water Level Drop (Inches)	Percolatio n Rate (Min./Inch )	Total Depth of Percolation Hole
11:12 11:42	30	44	46	2.00	15	56.00
11:42 12:12	30	44	45	1.00	30	56.00
12:12 12:42	30	42	45	3.00	10	56.00
12:42 13:12	30	41	42	1.00	30	53.00
13:12 13:42	30	41	42	1.00	30	53.00
13:42 14:12	30	41	42	1.00	30	53.00
14:12 14:42	30	41	42	1.00	30	53.00
14:42 15:11	29	41	42	1.00	29	53.00
15:11 15:42	31	41	42	1.00	31	53.00
15:42 16:12	30	41	42	1.00	30	53.00
16:12 16:42	30	41	42	1.00	30	53.00
16:42 17:12	30	41	42	1.00	30	53.00

"It" is the tested infiltration rate. Time interval,  $\Delta t$  Initial Depth to Water, Do Final Depth to Water, Dr Total Depth of Test Hole, Dr 2Test Hole Radius, r The conversion equation is used: "Havg" is the average head height over the time interval.

It =  $\frac{\Delta H \ 60 \ r}{\Delta t(r+2Havg)}$ 

Time interval ∆t	Initial Water H o	Final Water Hf	Total Depth of Test Hole D t	Raduis of Perc Hole r	ΔН	H Avg	ΔΗ 60 r)/(Δt (r+2Havg)) It	ELAPSED TIME Δt
30.00	12.00	10.00	56.00	4.00	2.00	11.00	0.62	30.00
30.00	12.00	11.00	56.00	4.00	1.00	11.50	0.30	60.00
30.00	14.00	11.00	56.00	4.00	3.00	12.50	0.83	90.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	120.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	150.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	180.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	210.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	240.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	270.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	300.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	330.00
30.00	12.00	11.00	53.00	4.00	1.00	11.50	0.30	360.00



Job No.:	151015-12	A			Tested By:	RCG	
Job Name:	Rancho Bo	nito Town Home	es				
Test Hole	Number:	P-3	Test F	lole Diamet	er (inches):	8	
Soil Classif	ication:	SM		Date	e Excavated:	12/28/2015	
Test Hole	Depth (ft):	4		1	Date Tested:	12/30/2015	
			Time Interva	l of Presoak			
Date / Time	e		0				
Start	12/30/1	5 11:13	Amount of \	Nater Used	Comments		
Stop	12/30/1	5 17:13	0				
Time	Time Interval (min.)	Initial Water Level (Inches)	Final Water Level (Inches)	Water Level Drop (Inches)	Percolatio n Rate (Min./Inch )	Total Depth of Percolation Hole	Time intervo Δt
11:13	20	41	45	4.00	0	F2 00	20.00
11:43	- 30	41	45	4.00	8	53.00	30.00
11:43	20	10	42	2.00	10	52.00	20.00
12:13	- 30	40	43	3.00	10	52.00	30.00
12:13	20	26				10.00	20.00
12:43	- 30	36	40	4.00	8	48.00	30.00
12:43							
13:13	30	34	38	4.00	8	48.00	30.00
13:13					_		
13:43	30	34	38	4.00	8	48.00	30.00
13.43							
14.13	30	34	36	2.00	15	48.00	30.00
14.13							
14:43	30	34	37	3.00	10	46.00	30.00
14:43							
15:13	30	33	35	2.00	15	46.00	30.00
15:13							
15:43	30	33	35	2.00	15	45.00	30.00
15:43							
16:13	30	32	34	2.00	15	44.00	30.00
16.13							
16:43	30	32	34	2.00	15	44.00	30.00
16:43							
17:13	30	31	33	2.00	15	43.00	30.00
	1						

"It" is the tested infiltration rate. Time interval,  $\Delta t$  Initial Depth to Water, D0 Final Depth to Water, Dr Total Depth of Test Hole, DT 2Test Hole Radius, r The conversion equation is used: "Havg" is the average head height over the time interval.

 $It = \frac{\Delta H 60 r}{\Delta t (r+2 Havg)}$ 

Time interval ∆t	Initial Water H o	Final Water Hf	Total Depth of Test Hole D t	Raduis of Perc Hole r	ΔН	H Avg	ΔΗ 60 r)/(Δt (r+2Havg)) It	ELAPSED TIME Δt
30.00	12.00	8.00	53.00	4.00	4.00	10.00	1.33	30.00
30.00	12.00	9.00	52.00	4.00	3.00	10.50	0.96	60.00
30.00	12.00	8.00	48.00	4.00	4.00	10.00	1.33	90.00
30.00	14.00	10.00	48.00	4.00	4.00	12.00	1.14	120.00
30.00	14.00	10.00	48.00	4.00	4.00	12.00	1.14	150.00
30.00	14.00	12.00	48.00	4.00	2.00	13.00	0.53	180.00
30.00	12.00	9.00	46.00	4.00	3.00	10.50	0.96	210.00
30.00	13.00	11.00	46.00	4.00	2.00	12.00	0.57	240.00
30.00	12.00	10.00	45.00	4.00	2.00	11.00	0.62	270.00
30.00	12.00	10.00	44.00	4.00	2.00	11.00	0.62	300.00
30.00	12.00	10.00	44.00	4.00	2.00	11.00	0.62	330.00
30.00	12.00	10.00	43.00	4.00	2.00	11.00	0.62	360.00



Job No.:	151015-12	A			Tested By:	RCG	
Job Name:	Rancho Bo	nito Town Hom	es				_
Test Hole I	Number:	P-4	Test H	lole Diamet	er (inches):	8	
Soil Classif	ication:	SM		Dat	e Excavated:	12/28/2015	
Test Hole (	Depth (ft):	3		I	Date Tested:	12/30/2015	
			- Time Interva	l of Presoak			•
Date / Time	e		0				
Start	12/30/1	5 11:14	Amount of \	Nater Used	Comments		
Stop	12/30/1	5 17:14	0				
			Final		Deveoletie	Total Doubh	1 <b>-</b>
Time	Time Interval (min.)	Initial Water Level (Inches)	Water Level (Inches)	Water Level Drop (Inches)	n Rate (Min./Inch )	of Percolation Hole	
11:14 11:44	30	27	29	2.00	15	39.00	
11:44	30	27	27	0.00	-	39.00	
12:14							
12:14	30	23	24	1.00	30	35.00	
12:44	30	23	24	1.00	30	35.00	
13:14	30	23	24	1.00	30	35.00	
13:44 13:44				4.00	20	25.00	-
14:14	- 30	23	24	1.00	30	35.00	
14:14	30	23	24	1.00	30	35.00	
14:44 15:14	30	23	23	0.00	-	35.00	
15:14 15:44	30	23	24	1.00	30	35.00	
15:44 16:14	30	23	24	1.00	30	35.00	
16:14 16:44	30	23	24	1.00	30	35.00	
16:44 17:14	30	23	24	1.00	30	35.00	
				-			

"It" is the tested infiltration rate. Time interval,  $\Delta t$  Initial Depth to Water, Do Final Depth to Water, Df Total Depth of Test Hole, DT 2Test Hole Radius, r The conversion equation is used: "Havg" is the average head height over the time interval.

 $It = \frac{\Delta H \ 60 \ r}{\Delta t (r+2 Havg)}$ 

Time interval ∆t	Initial Water H o	Final Water Hf	Total Depth of Test Hole D t	Raduis of Perc Hole r	ΔН	H Avg	ΔH 60 r)/(Δt (r+2Havg)) It	ELAPSED TIME Δt
30.00	12.00	10.00	39.00	4.00	2.00	11.00	0.62	30.00
30.00	12.00	12.00	39.00	4.00	0.00	12.00	0.00	60.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	90.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	120.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	150.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	180.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	210.00
30.00	12.00	12.00	35.00	4.00	0.00	12.00	0.00	240.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	270.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	300.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	330.00
30.00	12.00	11.00	35.00	4.00	1.00	11.50	0.30	360.00



	RCG					
JOD Name:						
Test Hole N	Number:	P-5	Test F	lole Diamet	er (inches):	8
Soil Classif	ication:	SM		Date	e Excavated:	12/28/2015
Test Hole L	Depth (ft):	3			Date Tested:	12/30/2015
Data / Time	_		l ime Interva	l of Presoak		
Date / Time Start	12/20/1	5 11.15	Amount of 1	Nator Llood	Commonte	
Ston	12/30/1	5 11.15 5 17·15		water Oseu /	comments	
5100	12/30/1	5 17.15			_	
Time	Time Interval (min.)	Initial Water Level (Inches)	Percolatio n Rate (Min./Inch )	Total Depth oj Percolation Hole		
11:15 11:45	30	42	44	2.00	15	58.00
11:45 12:15	30	42	42	0.00	-	56.00
12:15 12:45	30	39	39	0.00	-	51.00
12:45 13:15	30	39	40	1.00	30	51.00
13:15 13:45	30	39	39	0.00	-	51.00
13:45 14:15	30	39	40	1.00	30	51.00
14:15 14:45	30	39	39	0.00	-	51.00
14:45	30	39	39	0.00	-	51.00
15:15 15:15	30	39	39	0.00	-	51.00
15:45 16:15	30	39	40	1.00	30	51.00
16:15 16:45	30	39	40	1.00	30	51.00
16:45 17:15	30	39	39	0.00	-	51.00

"It" is the tested infiltration rate.

Time interval, ∆t Initial Depth to Water, D₀ Final Depth to Water, D₁ Total Depth of Test Hole, D⊤ 2Test Hole Radius, r The conversion equation is used: "Havg" is the average head height over the time interval.

It =  $\frac{\Delta H \ 60 \ r}{\Delta t(r+2 Havg)}$ 

Time interval ∆t	Initial Water H o	Final Water Hf	Total Depth of Test Hole D t	Raduis of Perc Hole r	ΔН	H Avg	ΔH 60 r)/(Δt (r+2Havg)) It	ELAPSED TIME Δt
30.00	16.00	14.00	58.00	4.00	2.00	15.00	0.47	30.00
30.00	14.00	14.00	56.00	4.00	0.00	14.00	0.00	60.00
30.00	12.00	12.00	51.00	4.00	0.00	12.00	0.00	90.00
30.00	12.00	11.00	51.00	4.00	1.00	11.50	0.30	120.00
30.00	12.00	12.00	51.00	4.00	0.00	12.00	0.00	150.00
30.00	12.00	11.00	51.00	4.00	1.00	11.50	0.30	180.00
30.00	12.00	12.00	51.00	4.00	0.00	12.00	0.00	210.00
30.00	12.00	12.00	51.00	4.00	0.00	12.00	0.00	240.00
30.00	12.00	12.00	51.00	4.00	0.00	12.00	0.00	270.00
30.00	12.00	11.00	51.00	4.00	1.00	11.50	0.30	300.00
30.00	12.00	11.00	51.00	4.00	1.00	11.50	0.30	330.00
30.00	12.00	12.00	51.00	4.00	0.00	12.00	0.00	360.00



	Geotechnical Boring Log MW-1										
Date: December 28, 2015Project Name: Rancho Bonito Town HomesPage: 1 of 1Project Number: 151015-12ALogged By: TJ											
Project	Numbe	r: 151	015-1	2A		Logged By: TJ					
Drilling	g Compa	ny:				Type of Rig:					
Drive V	Veight (l	lbs): 1	140			Drop (in): 30 Hole Diameter (in): 8					
Top of	Hole Ele	vatio	n (ft):			Hole Location: See Geotechnical Map					
Depth (ft)	Blow Count Per Foot	Sample Depth	Dry Density (pcf	Moisture (%)	Classification Symbol	MATERIAL DESCRIPTION					
0						Old Alluvial Fan Deposits (Qof):					
					SC SM	Clayey SAND; reddish brown, moist, medium dense Silty SAND; reddish brown, moist, dense					
5 -						Medium dense					
10						Light yellowish brown, very dense					
10 -											
						Refusal at 12 feet					
						End of Boring 12 feet					
						No Groundwater					
15 -											
	_										
20 -											
25 -											
30	_										
	4221	7 Rio	Nedo	Roa	d, Suit	e A-104, Temecula, CA 92590					



Geotec and Ma		Ţ	DRAWN BY C	REVISION	DWG XREFS	SCALE 1	DATE F	PROJECT NO. 1	<b>CLIENT</b> S	PROJECT R		CITY OF I	LOCATED ON THE SOUT	INFILTH
chnical, Er aterials Te	Ç	N	ĊS			:120	EBRUARY 2016	51015-12A	HERMAN AND GAR	ANCHO BONITA DE	APN 360-3	MENIFEE, RIVERSIC	'H SIDE OF GARBANI ROAD,	RATION L
wironmenta sting Cons	Ć		PLATE						BANI, LLC	VELOPMENT	50-006	IE COUNTY, CALIFC	BETWEEN SHERMAN ROAD	OCATION
al, 5ultants			1 OF 1									IRNIA	AND HAUN ROAD	MAP





Limits of Report

Percolation Test Location

P-4

ī