State of California

Governor's Office of Emergency Services (Cal OES)

NOTICE OF EXEMPTION

TO: Office of Planning and Research 1400 Tenth Street Sacramento, CA 95814

FROM: Office of Emergency Services

3650 Schriever Ave Mather, CA 95655

PROJECT TITLE: Seismic Monitoring Station Upgrade

COUNTY: Lake

PROJECT APPLICANT: U.S. Geological Survey (CEEWS Project #: 6087-6)

PROJECT LOCATION: Pine Summit Drive, Middletown, CA; Lat/Lon: 38.81434/-122.68277; Dot Map ID: UG1024;

Station Name/Site Code: Boggs Mountain/NC.GBG

DESCRIPTION OF PURPOSE AND NATURE OF THE PROJECT:

By upgrading from antiquated analog recording systems to state-of-the-art earthquake recording and telemetry equipment, this station will be able to contribute continuous seismic data to the CA Earthquake Early Warning System (CEEWS) and ShakeAlert, designed to potentially save thousands of lives during a large earthquake. prevent critical infrastructure damage, and expedite recovery following a large earthquake.

With permission from the property owner secured, USGS plans to upgrade and operate the seismic monitoring station at the Lat/Lon location noted above. The existing equipment enclosures will be removed and replaced with two new aluminum enclosures (2' x 3' x 21"H) mounted to 6" thick concrete pads: one concrete pad at grade (maximum 6" depth) and the second concrete pad at a depth of typically 16" below grade. The existing antenna and PV mast at the site will be replaced with an ~8' tall steel pipe which will be mounted to one enclosure and concrete pad and hold the 2'x4' solar array and telemetry antenna. The two enclosures will be connected by flexible conduit in a shallow trench (6" deep, 6" wide) about 25ft long; this trench will be filled to grade after installation. A ground rod will be driven to a depth of 8' proximate to the battery/radio enclosure; additionally, a 2gauge wire will be buried in a 12" deep, 6" wide trench around the exterior of the enclosure. All excavation will be dug by hand or mini-excavator, depending on site accessibility. There are no hazardous substances involved during construction nor as components of the site. If necessary, a small generator will be used to power a handloaded concrete mixer and any other tools needed for the construction. Construction/installation takes 3 days and covers a total of 175sq.ft, (5'x35').

PUBLIC AGENCY APPROVING PROJECT: Office of Emergency Services (Cal OES) DIVISION OR UNIT CARRYING OUT PROJECT: CA Earthquake Early Warning Program

EXEMPT STATUS:

Categorical Exemption. Class 3, CEQA Guidelines Section15303 (New Construction), Class 4 Section15304 (Minor Alterations to Land) and Class 6 Section 15306 (Information Collection).

REASONS WHY PROJECT IS EXEMPT:

This project is exempt in accordance with Class 3 as described above; construction of new small weatherproof enclosures to operate seismic sensor equipment for the purpose of data collection (Class 6). In accordance with Class 4, the project described above consists of minor public or private alterations in the condition of land and/or vegetation which do not involve removal of healthy, mature, scenic trees. None of the exceptions to a notice of exemption apply.

APPLICANT CONTACT: Lind Gee

TELEPHONE: 650-329-5656

TITLE:

TITLE:

NCSN Project Chief

EMAIL: Igee@usgs.gov

LEAD AGENCY CONTACT:

Rvan Arba Program Manager III

TELEPHONE: 916-845-8132

SIGNED BY LEAD AGENCY:

MAR 06 2019

Signature:

Governor's Office of Planning & Research

Title:

STATE CLEARINGHOUSE