

Indian and Ramona Warehouse

TRAFFIC IMPACT ANALYSIS
CITY OF PERRIS

PREPARED BY:

Aric Evatt, PTP aevatt@urbanxroads.com (949) 336-5978

Charlene So, PE cso@urbanxroads.com (949) 336-5982

FEBRUARY 14, 2019

11704-06 TIA Report.docx

TABLE OF CONTENTS

	_	F CONTENTS	
		CES	
		XHIBITS	
		ABLES	
		ABBREVIATED TERMS	
1	IN	TRODUCTION	1
	1.1	Project Overview	1
	1.2	Analysis Scenarios	3
	1.3	Study Area	4
	1.4	Summary of Project Impacts and Mitigation Measures	7
	1.5	Local and Regional Funding Mechanisms	8
	1.6	On-Site Roadway Improvements	10
	1.7	Site Access Improvements	12
	1.8	Queuing Analysis at the Project Driveways	13
	1.9	Truck Access	14
	1.10	Sight Distance Analysis	14
2	М	ETHODOLOGIES	19
	2.1	Level of Service	
	2.2	Intersection Capacity Analysis	
	2.3	Traffic Signal Warrant Analysis Methodology	
	2.4	Minimum Level of Service (LOS)	
	2.5	CEQA Compliance and Documentation	
	2.6	SB 743 Requirements	
3		EEA CONDITIONS	
3			
	3.1	Existing Circulation Network	
	3.2	General Plan Circulation Elements	
	3.3	Truck Routes	
	3.4	Transit Service	
	3.5	Bicycle & Pedestrian Facilities	
	3.6	Existing Traffic Counts	
	3.7	Intersection Operations Analysis	
	3.8	Traffic Signal Warrants Analysis	
4	PR	OJECTED FUTURE TRAFFIC	43
	4.1	Project Trip Generation	43
	4.2	Project Trip Distribution	45
	4.3	Modal Split	
	4.4	Project Trip Assignment	
	4.5	Background Traffic	49
	4.6	Cumulative Development Traffic	
	4.7	Traffic Forecasts	
	4.8	Near-Term Traffic Conditions	56
5	E+	P TRAFFIC CONDITIONS	57
	5.1	Roadway Improvements	57
		, , , , , , , , , , , , , , , , , , , ,	



	5.2	E+P Traffic Volume Forecasts	57
	5.3	Intersection Operations Analysis	57
	5.4	Traffic Signal Warrants Analysis	
6	E	A AND EAP (2020) TRAFFIC ANALYSIS	61
	6.1	Roadway Improvements	61
	6.2	EA (2020) Traffic Volume Forecasts	61
	6.3	EAP (2020) Traffic Volume Forecasts	61
	6.4	Intersection Operations Analysis	61
	6.5	Traffic Signal Warrants Analysis	
7	E	AC AND EAPC (2020) TRAFFIC CONDITIONS	67
	7.1	Roadway Improvements	67
	7.2	EAC (2020) Traffic Volume Forecasts	67
	7.3	EAPC (2020) Traffic Volume Forecasts	67
	7.4	Intersection Operations Analysis	67
	7.5	Traffic Signal Warrants Analysis	73
	7.6	Summary of Findings	73
R	R	REFERENCES	75



APPENDICES

APPENDIX 1.1: TRAFFI	IC STUDY SCOPING AGREEME	:N I	
APPENDIX 1.2: SITE AI	DJACENT QUEUING ANALYSIS	S	
APPENDIX 3.1: EXISTII	NG TRAFFIC COUNTS – MAY 2	2018	
APPENDIX 3.2: EXISTII	NG (2018) CONDITIONS INTE	RSECTION OPERATIONS	ANALYSIS WORKSHEETS
APPENDIX 5.1: E+P CC	ONDITIONS INTERSECTION OF	PERATIONS ANALYSIS W	ORKSHEETS
APPENDIX 5.2: E+P CC	ONDITIONS TRAFFIC SIGNAL \	WARRANT ANALYSIS WO	RKSHEETS
APPENDIX 6.1: EA (20)	20) CONDITIONS INTERSECTI	ON OPERATIONS ANALY	SIS WORKSHEETS
APPENDIX 6.2: EAP (2	020) CONDITIONS INTERSECT	TION OPERATIONS ANAL	YSIS WORKSHEETS
APPENDIX 6.3: EAP (2	020) CONDITIONS TRAFFIC SI	GNAL WARRANT ANALY	SIS WORKSHEETS
APPENDIX 7.1: EAC (2	020) CONDITIONS INTERSECT	TION OPERATIONS ANAL	YSIS WORKSHEETS
APPENDIX 7.2: EAPC (2020) CONDITIONS INTERSEC	CTION OPERATIONS ANA	LYSIS WORKSHEETS
APPENDIX 7.3: EAPC (2020) CONDITIONS TRAFFIC	SIGNAL WARRANT ANAL	YSIS WORKSHEETS



This Page Intentionally Left Blank



LIST OF EXHIBITS

EXHIBIT 1-1: PRELIMINARY SITE PLAN	2
EXHIBIT 1-2: LOCATION MAP	5
EXHIBIT 1-3: SUMMARY OF DEFICIENT INTERSECTIONS BY ANALYSIS SCENARIO	6
EXHIBIT 1-4: SITE ADJACENT ROADWAY AND SITE ACCESS RECOMMENDATIONS	11
EXHIBIT 1-5: TRUCK ACCESS	15
EXHIBIT 1-6: SIGHT DISTANCE	16
EXHIBIT 3-1: EXISTING NUMBER OF THROUGH LANES AND INTERSECTION CONTROLS	26
EXHIBIT 3-2: CITY OF PERRIS GENERAL PLAN CIRCULATION ELEMENT	
EXHIBIT 3-3: CITY OF PERRIS GENERAL PLAN ROADWAY CROSS-SECTIONS	28
EXHIBIT 3-4: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN CIRCULATION PLAN	29
EXHIBIT 3-5: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN CROSS-SECTIONS	30
EXHIBIT 3-6: CITY OF PERRIS TRUCK ROUTES	31
EXHIBIT 3-7: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN TRUCK ROUTE PLAN	32
EXHIBIT 3-8: EXISTING TRANSIT ROUTES	
EXHIBIT 3-9: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN MASS TRANSIT ROUTES	34
EXHIBIT 3-10: CITY OF PERRIS PROPOSED BIKEWAYS AND TRAIL IMPROVEMENTS	36
EXHIBIT 3-11: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN TRAIL SYSTEM	37
EXHIBIT 3-12: EXISTING PEDESTRIAN FACILITIES	38
EXHIBIT 3-13: EXISTING (2018) TRAFFIC VOLUMES (IN PCE)	
EXHIBIT 3-14: EXISTING (2018) SUMMARY OF LOS	
EXHIBIT 4-1: PROJECT (PASSENGER CAR) TRIP DISTRIBUTION	47
EXHIBIT 4-2: PROJECT (TRUCK) TRIP DISTRIBUTION	
EXHIBIT 4-3: PROJECT ONLY TRAFFIC VOLUMES (IN PCE)	
EXHIBIT 4-4: CUMULATIVE DEVELOPMENT LOCATION MAP	
EXHIBIT 4-5: CUMULATIVE ONLY TRAFFIC VOLUMES (IN PCE)	
EXHIBIT 5-1: E+P TRAFFIC VOLUMES (IN PCE)	
EXHIBIT 5-2: E+P SUMMARY OF LOS	
EXHIBIT 6-1: EA (2020) TRAFFIC VOLUMES (IN PCE)	
EXHIBIT 6-2: EAP (2020) TRAFFIC VOLUMES (IN PCE)	
EXHIBIT 6-3: EA (2020) SUMMARY OF LOS	
EXHIBIT 6-4: EAP (2020) SUMMARY OF LOS	
EXHIBIT 7-1: EAP (2020) TRAFFIC VOLUMES (IN PCE)	
EXHIBIT 7-2: EAPC (2020) TRAFFIC VOLUMES (IN PCE)	69
EXHIBIT 7-3: EAC (2020) SUMMARY OF LOS EXHIBIT 7-4: EAPC (2020) SUMMARY OF LOS	70



This Page Intentionally Left Blank



LIST OF TABLES

TABLE 1-1: INTERSECTION ANALYSIS LOCATIONS	
TABLE 1-2: NPRBBD FACILITES	10
TABLE 2-1: SIGNALIZED INTERSECTION LOS THRESHOLDS	
TABLE 2-2: UNSIGNALIZED INTERSECTION LOS THRESHOLDS	20
TABLE 2-3: TRAFFIC SIGNAL WARRANT ANALYSIS LOCATIONS	21
TABLE 3-1: INTERSECTION ANALYSIS FOR EXISTING (2018) CONDITIONS	42
TABLE 4-1: PROJECT TRIP GENERATION RATES	44
TABLE 4-2: PROJECT TRIP GENERATION SUMMARY	46
TABLE 4-3: CUMULATIVE DEVELOPMENT LAND USE SUMMARY	
TABLE 5-1: INTERSECTION ANALYSIS FOR E+P CONDITIONS	60
TABLE 6-1: INTERSECTION ANALYSIS FOR EA (2020) AND EAP (2020) CONDITIONS	
TABLE 7-1: INTERSECTION ANALYSIS FOR FAC (2020) AND FAPC (2020) CONDITIONS	



This Page Intentionally Left Blank



LIST OF ABBREVIATED TERMS

(1) Reference

ADT Average Daily Traffic

AASHTO American Association of State Highway Transportation Officials

APZ Accident Potential Zone

CA MUTCD California Manual on Uniform Traffic Control Devices

Caltrans California Department of Transportation
CEQA California Environmental Quality Act
CMP Congestion Management Program

DIF Development Impact Fee

E+P Existing Plus Project

EA Existing plus Ambient Growth

EAC Existing plus Ambient Growth plus Cumulative
EAP Existing plus Ambient Growth plus Project

EAPC Existing plus Ambient Growth plus Project plus Cumulative

HCM Highway Capacity Manual

ITE Institute of Transportation Engineers

LOS Level of Service N/A Not Applicable

NP No Project (or Without Project)

NPRBBD North Perris Road and Bridge Benefit District

PCE Passenger Car Equivalents

PHF Peak Hour Factor

Project Indian and Ramona Warehouse

PVCC SP Perris Valley Commerce Center Specific Plan

RTA Riverside Transit Authority

RTP/SCS Regional Transportation Plan/Sustainable Communities

Strategy

SCAG Southern California Association of Governments
SCAQMD South Coast Air Quality Management District

sf Square Feet

TIA Traffic Impact Analysis
TSF Thousand Square Feet

TUMF Transportation Uniform Mitigation Fee

WP With Project

WRCOG Western Riverside Council of Governments

V/C Volume to Capacity



VMT Vehicle Miles Traveled



1 INTRODUCTION

This report presents the results of the traffic impact analysis (TIA) for the proposed Indian and Ramona Warehouse development ("Project"), located on the northwest corner of Indian Avenue and Ramona Expressway, within the City of Perris' *Perris Valley Commerce Center Specific Plan* (PVCC SP) as shown on Exhibit 1-1.

The purpose of this traffic impact analysis is to evaluate the potential impacts related to traffic and circulation system deficiencies that may result from the development of the proposed Project, and to recommend improvements to mitigate impacts considered significant in comparison to established regulatory thresholds and to achieve acceptable circulation system operational conditions. This report has been prepared in accordance with the Project Traffic Study Scoping agreement through consultation with and approval from the City of Perris, which is provided in Appendix 1.1 of this report.

1.1 PROJECT OVERVIEW

The Project is proposed to consist of a single high-cube transload and short-term storage warehouse building at approximately 428,730 square feet (sf). The Project is anticipated to be constructed in a single phase by the year 2020. The proposed Project land use is consistent with the PVCC SP. The designated land use and zoning within the PVCCP SP is Light Industrial within the Accident Potential Zone (APZ) I and APZ II overlay.

Vehicular and truck traffic access will be provided via the following driveways (see Exhibit 1-1):

- Driveway 1 & Ramona Expressway Right-in/right-out access only for passenger cars
- Indian Avenue & Driveway 2/Perry Street Full access only for trucks
- Indian Avenue & Driveway 3 Right-in/right-out access only for passenger cars

The minimum intersection spacing required on Ramona Expressway is 2,640 feet. Driveway 1 on Ramona Expressway does not meet the required spacing and is therefore restricted to right-in/right-out access only. Indian Avenue requires 660 feet of space between intersections. Driveway 2 meets the intersections spacing criteria and has been evaluated assuming full access, while Driveway 3 on Indian Avenue does not meet the spacing criteria and has therefore been evaluated assuming right-in/right-out access only. Regional access to the Project site is provided via the I-215 Freeway and Ramona Expressway for passenger cars and at Harley Knox Boulevard for heavy trucks.

Trips generated by the Project's proposed land uses have been estimated based on trip generation rates collected by the Institute of Transportation Engineers (ITE) <u>Trip Generation Manual</u>, 10th Edition, 2017. (1) The Project is estimated to generate a net total of 897 passenger-car-equivalent (PCE) trip-ends per day on a typical weekday with approximately 50 net AM PCE peak hour trips and 58 net PM PCE peak hour trips. The assumptions and methods used to estimate the Project's trip generation characteristics are discussed in greater detail in Section 4.1 *Project Trip Generation* of this report.



PVCC SP BOUNDARY PERRY ST. DWY. 2 (T) (FULL) CEQA STUDY AREA DWY. 3 (P) (RIRO) DWY 1. (P) 428,730 S.F. INDIAN AV. (RIRO) 1281 **RAMONA EXWY.**

EXHIBIT 1-1: PRELIMINARY SITE PLAN



RIRO = RIGHT-IN/RIGHT-OUT ONLY ACCESS

P = PASSENGER CARS ONLY

T = TRUCKS ONLY





1.2 ANALYSIS SCENARIOS

For the purposes of this traffic study, potential impacts to traffic and circulation have been assessed for each of the following conditions:

- Existing (2018)
- Existing Plus Project (E+P)
- Existing Plus Ambient Growth (EA) (2020)
- Existing Plus Ambient Growth Plus Project (EAP) (2020)
- Existing Plus Ambient Growth Plus Cumulative Projects (EAC) (2020)
- Existing Plus Ambient Growth Plus Project Plus Cumulative Projects (EAPC) (2020)

1.2.1 Existing (2018) Conditions

Information for Existing (2018) conditions is disclosed to represent the baseline traffic conditions as they existed at the time this report was prepared. Traffic counts were conducted in May 2018 based on vehicle classification and were converted to PCE due to the presence of heavy trucks within the study area.

1.2.2 EXISTING PLUS PROJECT CONDITIONS

The Existing Plus Project (E+P) analysis determines any significant traffic impacts and circulation system deficiencies that would occur on the existing roadway system in the scenario of the Project being placed upon Existing conditions.

1.2.3 EXISTING PLUS AMBIENT GROWTH AND EXISTING PLUS AMBIENT GROWTH PLUS PROJECT (2020) CONDITIONS

The EA and EAP (2020) conditions analyses determines the traffic impacts based on a comparison of the EAP (2020) traffic conditions to EA (2020) conditions. To account for background traffic growth, an ambient growth factor from Existing (2018) conditions of 6.09% (3 percent per year, compounded over 2 years) is included for EA and EAP (2020) traffic conditions. As discussed below, in order to conduct a more conservative analysis, other cumulative development projects are not included as part of the EAP (2020) analysis.

1.2.4 EXISTING PLUS AMBIENT GROWTH PLUS CUMULATIVE AND EXISTING PLUS AMBIENT GROWTH PLUS PROJECT PLUS CUMULATIVE (2020) CONDITIONS

To account for growth in traffic between Existing (2018) conditions and the Project Opening Year (2020), a traffic growth rate of 6.09% was assumed (3 percent per year, compounded over 2 years). The 3.0 percent annual growth rate is intended to capture non-specific ambient traffic growth.

Conservatively, the TIA estimates of area traffic growth then add traffic generated by other known or probable related projects. These related projects are at least in part already accounted for in the assumed 6.09% total ambient growth in traffic noted above; and in some instances, these related projects would likely not be implemented and operational within the 2020 Opening



Year time frame assumed for the Project. The resulting traffic growth rate utilized in the TIA (6.09 percent ambient growth + traffic generated by related projects) would therefore tend to overstate rather than understate background cumulative traffic impacts under 2020 conditions.

1.3 STUDY AREA

To ensure that this TIA satisfies the City of Perris' traffic study requirements, Urban Crossroads, Inc. prepared a Project traffic study scoping package for review by City of Perris staff prior to the preparation of this report. The scoping agreement provides an outline of the Project study area, trip generation, trip distribution, and analysis methodology and is included in Appendix 1.1.

The 4 study area intersections shown on Exhibit 1-2 and listed in Table 1-1 were selected for this TIA based on the City's Traffic Study Guidelines and in consultation with City of Perris staff. Pursuant to the Traffic Study Guidelines, the City requires analysis of intersections where the Project would contribute 50 or more peak hour trips. Based on the location of the Project site, the Project traffic dissipates between the Project site and the state facilities (intersections or Freeway segments). Based on the Project trip distributions, the Project only contributes 13 AM PCE peak hour trips and 24 PM PCE peak hour trips to the I-215 and Ramona Expressway ramps. Since the Project does not contribute 50 or more peak hour trips to any State facilities (intersections or freeway segments), assessment of state facilities is not required as the Project's traffic contribution to the State facilities is considered less than significant. The project trip generation, distribution, and volumes are further explained in Chapter 4 *Project Future Traffic* of this TIA.

TABLE 1-1: INTERSECTION ANALYSIS LOCATIONS

ID	Intersection Location	Jurisdiction	CMP?
1	Driveway 1 & Ramona Expressway – Future Intersection	City of Perris	No
2	Indian Avenue & Driveway 2/Perry Street	City of Perris	No
3	Indian Avenue & Driveway 3 – Future Intersection	City of Perris	No
4	Indian Avenue & Ramona Expressway	City of Perris	No

^{*} Note: CMP = Congestion Management Program

The intent of a Congestion Management Program (CMP) is to more directly link land use, transportation, and air quality, thereby prompting reasonable growth management programs that will effectively utilize new transportation funds, alleviate traffic congestion and related impacts, and improve air quality. Counties within California have developed CMPs with varying methods and strategies to meet the intent of the CMP legislation. None of the study area intersections are identified as CMP facilities in the County of Riverside CMP. (2)



PERRY ST. DWY. 2 (T) (FULL) CEQA STUDY AREA DWY. 3 (P) (RIRO) DWY 1. (P) INDIAN AV. (RIRO)

EXHIBIT 1-2: LOCATION MAP



RAMONA EXWY.



■ EXISTING INTERSECTION ANALYSIS LOCATION





EXHIBIT 1-3: SUMMARY OF DEFICIENT INTERSECTIONS BY ANALYSIS SCENARIO

#	Intersection	Existing (2018)	E+P	EA (2020)	EAP (2020)	EAC (2020)	EAPC (2020)
1	Dwy. 1 & Ramona Exwy.	NA		NA		NA	
2	Indian Av. & Dwy. 2 / Perry St.		•	•	•		
3	Indian Av. & Dwy. 3	NA	•	NA	•	NA	
4	Indian Av. & Ramona Exwy.						

LEGEND:



- AM PEAK HOUR



■ PM PEAK HOUR



● LOS E



LOS F

NA - NOT AN ANALYSIS LOCATION FOR THIS SCENARIO



1.4 SUMMARY OF PROJECT IMPACTS AND MITIGATION MEASURES

This section provides a summary of direct Project impacts and associated mitigation measures. Section 2 *Methodologies* provides information on the methodologies used in the analyses and Section 5 *E+P Traffic Analysis*, Section 6 *EA and EAP (2020) Traffic Analysis* and Section 7 *EAC and EAPC (2020) Traffic Analysis* include the detailed analyses. All the study area intersections operate at acceptable level of service (LOS) for all the scenarios (see Exhibit 1-3). Therefore, there are no direct Project impacts. Each project implementing the PVCC SP is required to incorporate applicable mitigation from the PVCC Specific Plan EIR. The relevant traffic mitigation measures from the PVCC Specific Plan EIR are identified in Section 1.4.1.

1.4.1 PVCC Specific Plan EIR Traffic Mitigation Measures

- **MM Trans 1** Future implementing development projects shall construct on-site roadway improvements pursuant to the general alignments and right-of-way sections set forth in the PVCC Circulation Plan, except where said improvements have previously been constructed.
- MM Trans 2 Sight distance at the project entrance roadway of each implementing development project shall be reviewed with respect to standard City of Perris sight distance standards at the time of preparation of final grading, landscape and street improvement plans.
- MM Trans 3 Each implementing development project shall participate in the phased construction of off-site traffic signals through payment of that project's fair share of traffic signal mitigation fees and the cost of other off-site improvements through payment of fair share mitigation fees which include TUMF (Transportation Uniform Mitigation Fee), DIF (Development Impact Fee), and the NPRBBD (North Perris Road and Bridge Benefit District). The fees shall be collected and utilized as needed by the City of Perris to construct the improvements necessary to maintain the required level of service and build or improve roads to their build-out level.
- MM Trans 4 Prior to the approval of individual implementing development projects, the Riverside Transit Agency (RTA) shall be contacted to determine if the RTA has plans for the future provision of bus routing in the project area that would require bus stops at the project access points. If the RTA has future plans for the establishment of a bus route that will serve the project area, road improvements adjacent to the project site shall be designed to accommodate future bus turnouts at locations established through consultation with the RTA. RTA shall be responsible for the construction and maintenance of the bus stop facilities. The area set aside for bus turnouts shall conform to RTA design standards, including the design of the contact between sidewalk and curb and gutter at bus stops and the use of ADA-compliant paths to the major building entrances in the project.



MM Trans 5 Bike racks shall be installed in all parking lots in compliance with City of Perris standards.

MM Trans 7 Implementing project-level traffic impact studies shall be required for all subsequent implementing development proposals within the boundaries of the PVCC as approved by the City of Perris Engineering Department. These subsequent traffic studies shall identify specific project impacts and needed roadway improvements to be constructed in conjunction with each implementing development project. All intersection spacing for individual tracts or maps shall conform to the minimum City intersection spacing standards. All turn pocket lengths shall conform at least to the minimum City turn pocket length standards. If any of the proposed improvements are found to be infeasible, the implementing development project applicant would be required to provide alternative feasible improvements to achieve levels of service satisfactory to the City.

MM Trans 8 Proposed mitigation measures resulting from project-level traffic impact studies shall be coordinated with the North Perris Road and Bridge Benefit District (NPRBBD) to ensure that they are in conformance with the ultimate improvements planned by the NPRBBD. The applicant shall be eligible to receive proportional credits against the NPRBBD for construction of project level mitigation that is included in the NPRBBD.

1.5 Local and Regional Funding Mechanisms

Transportation improvements throughout the City of Perris are funded through a combination of project mitigation, fair share contributions or development impact fee programs, such as TUMF program, the City's DIF program, or the NPRBBD program.

1.5.1 TRANSPORTATION UNIFORM MITIGATION FEE (TUMF) PROGRAM

The Western Riverside Council of Governments (WRCOG) is responsible for establishing and updating TUMF rates. The County may grant to developers a credit against the specific components of fees for the dedication of land or the construction of facilities identified in the list of improvements funded by each of these fee programs. Fees are based upon projected land uses and a related transportation need to address growth based upon a 2009 Nexus study.

TUMF is an ambitious regional program created to address cumulative impacts of growth throughout western Riverside County. Program guidelines are being handled on an iterative basis. Exemptions, credits, reimbursements and local administration are being deferred to primary agencies. The County of Riverside serves this function for the proposed Project. Fees submitted to the County are passed on to the WRCOG as the ultimate program administrator.

TUMF guidelines empower a local zone committee to prioritize and arbitrate certain projects. The Project is located in the Central Zone. The zone has developed a 5-year capital improvement program to prioritize public construction of certain roads. TUMF is focused on improvements necessitated by regional growth.



1.5.2 CITY OF PERRIS DEVELOPMENT IMPACT FEE (DIF) PROGRAM

In 1991, the City of Perris created a Development Impact Fee program to impose and collect fees from new residential, commercial and industrial development for the purpose of funding roadways and intersections necessary to accommodate City growth as identified in the City's General Plan Circulation Element. This DIF program has been successfully implemented by the City since 1991 and was updated in 2014. The City updated the DIF program to add new roadway segments and intersections necessary to accommodate future growth and to ensure that the identified street improvements would operate at or above the City's LOS performance threshold. The City's DIF program includes facilities that are not part of or which may exceed improvements identified and covered by the TUMF program. As a result, the pairing of the regional and local fee programs provides a more comprehensive funding and implementation plan to ensure an adequate and interconnected transportation system. Under the City's DIF program, the City may grant to developers a credit against specific components of fees when those developers construct certain facilities and landscaped medians identified in the list of improvements funded by the DIF program.

Similar to the TUMF Program, after the City's DIF fees are collected, they are placed in a separate interest-bearing account pursuant to the requirements of Government Code sections 66000 *et seq.* The timing to use the DIF fees is established through periodic capital improvement programs which are overseen by the City's Public Works Department. Periodic traffic counts, review of traffic accidents, and a review of traffic trends throughout the City are also periodically performed by City staff and consultants. The City uses this data to determine the timing of the improvements listed in its facilities list. The City also uses this data to ensure that the improvements listed on the facilities list are constructed before the LOS falls below the LOS performance standards adopted by the City. In this way, the improvements are constructed before the LOS falls below the City's LOS performance thresholds. The City's DIF program establishes a timeline to fund, design, and build the improvements.

The City has an established, proven track record with respect to implementing the City's DIF Program. Many of the roadway segments and intersections included within the study area for this Traffic Impact Analysis are at various stages of widening and improvement based on the City's collection of DIF fees. Under this Program, as a result of the City's continual monitoring of the local circulation system, the City insures that DIF improvements are constructed prior to when the LOS would otherwise fall below the City's established performance criteria.

1.5.3 North Perris Road and Bridge Benefit District (NPRBBD)

The NPRBBD is comprised of approximately 3,500 acres of land located within the northern portion of the City of Perris. The NPRBBD boundary is consistent with the boundary of the PVCC SP. As such, the Project will be subject to the NPRBBD. The purpose of the NPRBBD is to improve the efficiency of the financing of specific regional road and bridge improvements that are determined to provide benefit to the developing properties within the NPRBBD boundary. In addition, the NPRBBD includes additional improvements to supplement the TUMF and DIF network. NPRBBD fees are inclusive of TUMF and DIF. A significant portion of the fees collected through this mechanism are earmarked for use within the boundary sufficient to fully fund the



included improvements. The balance of TUMF is transmitted to WRCOG for use in addressing cumulative impacts elsewhere within Western Riverside County. The City treats the DIF component collected within the NPRBBD in a similar way to ensure the local circulation network outside the program boundaries is adequately addressed.

Table 1-2 lists each facility identified within the NPRBBD, the General Plan roadway classification and the current estimated construction cost for the facilities.

TABLE 1-2: NPRBBD FACILITES

Facility Name	General Plan Classification	Estimated Cost
Indian Avenue	Secondary Arterial	\$11,343,500
Perris Boulevard	Arterial	\$17,350,800
Redlands Avenue	Secondary Arterial	\$14,845,000
Harley Knox Boulevard	Arterial	\$31,813,700
Markham Street	Secondary Arterial	\$2,132,000
Ramona Expressway	Expressway	\$10,865,000
Morgan Street	Secondary Arterial	\$2,899,500
Rider Street	Secondary Arterial	\$3,803,000
Placentia Avenue	Arterial	\$18,705,900
Indian Avenue Bridge	Secondary Arterial	\$701,800
Harley Knox Boulevard Bridge	Arterial	\$4,210,800
Ramona Expressway Bridge	Expressway	\$2,105,800
Placentia Avenue Bridge	Arterial	\$6,316,200
Harley Knox Boulevard Interchange @ I-215	Arterial	\$17,371,000
Placentia Avenue Interchange @ I-215	Arterial	\$8,389,000
4-Lane Intersections – Traffic Signals	4 – Signal Locations	\$870,000
6-Lane Intersections – Traffic Signals	11 – Signal Locations	\$3,190,000
District Totals		\$156,913,000

The facilities identified within the NPRBBD provide additional benefit by providing alternate truck routes within the City of Perris. It should be noted that NPRBBD fees are to be paid in conjunction with TUMF and City DIF fees as a one-time fee payment to the City prior to the issuance of a building permit.


1.6 ON-SITE ROADWAY IMPROVEMENTS


The recommended site-adjacent roadway improvements for the Project are described below. Exhibit 1-4 illustrates the site-adjacent roadway improvement recommendations.

Ramona Expressway – Ramona Expressway is an east-west oriented roadway located along the Project's southern boundary. Construct Ramona Expressway at its ultimate half-section width as an Expressway (184-foot right-of-way) between the western Project boundary and Indian Avenue consistent with the PVCC SP and the City of Perris General Plan Circulation Element. The Project Applicant would improve Ramona Expressway as required by the final Conditions of Approval for the Project and applicable City of Perris standards.



EXHIBIT 1-4: SITE ADJACENT ROADWAY AND SITE ACCESS RECOMMENDATIONS





LEGEND:



STOP SIGN

= EXPRESSWAY (184' R.O.W.)
= SECONDARY ARTERIAL (94' R.O.W.)

← ■ LANE IMPROVEMENT

100 = RECOMMENDED MINIMUM TURN POCKET LENGTH

DEF = DEFACTO RIGHT TURN



Indian Avenue – Indian Avenue is a north-south oriented roadway located along the Project's eastern boundary. Construct Indian Avenue at its ultimate half-section width as a Secondary Arterial (94-foot right-of-way) between the eastern Project boundary (at the proposed Driveway 3) and Ramona Expressway consistent with the PVCC SP and the City of Perris General Plan Circulation Element. The Project Applicant would improve Indian Avenue as required by the final Conditions of Approval for the Project and applicable City of Perris standards.

1.7 SITE ACCESS IMPROVEMENTS

The recommended site access driveway improvements for the Project are described below. Exhibit 1-4 also illustrates the site access improvements. Construction of on-site and site adjacent improvements shall occur in conjunction with adjacent Project development activity or as needed for Project access purposes.

Driveway 1 & Ramona Expressway – Install a stop control on the southbound approach and construct the intersection with the following geometrics:

- Northbound Approach: Not Applicable (N/A)
- Southbound Approach (Project Driveway 1): One right turn lane.
- Eastbound Approach (Ramona Expressway): Three through lanes.
- Westbound Approach (Ramona Expressway): Three through lanes and a defacto right turn lane.

There is an existing raised median along Ramona Expressway that would prohibit left turns in and left turns out at this driveway.

Driveway 2 & Indian Avenue — Install traffic signal and construct the intersection with the following geometrics:

- Northbound Approach (Project Driveway 2): One left turn lane and one right turn lane.
- Southbound Approach: N/A
- Eastbound Approach (Indian Avenue): One through lane and one shared through-right turn lane.
- Westbound Approach (Indian Avenue): One left turn lane with a minimum of 150-feet of storage and two through lanes.

Although Driveway 2 is not anticipated to warrant a traffic signal based on future projected daily traffic, the Project is proposing the installation of a traffic signal as it is proposed to accommodate access to trucks heading to and from the north (Harley Knox Boulevard via Indian Avenue).

Indian Avenue & Driveway 3 – Install a stop control on the eastbound approach and construct the intersection with the following geometrics:

- Northbound Approach (Indian Avenue): Two through lanes.
- Southbound Approach (Indian Avenue): One through lane and one shared through-right turn lane.
- Eastbound Approach (Project Driveway 3): One right turn lane.
- Westbound Approach: N/A



There is an existing raised median along Indian Avenue that would prohibit left turns in and left turns out at this driveway.

Indian Avenue & Ramona Expressway – Maintain the existing traffic control (traffic signal) and lane geometrics.

Wherever necessary, roadways adjacent to the Project, site access points and site-adjacent intersections will be constructed to be consistent with the identified roadway classifications and respective cross-sections in the City of Perris General Plan Circulation Element.

1.8 Queuing Analysis at the Project Driveways

A queuing analysis was conducted along the site adjacent roadways of Ramona Expressway and Indian Avenue for EAPC (2020) traffic conditions to determine the turn pocket lengths necessary to accommodate near term 95th percentile queues. The analysis was conducted for the weekday AM and weekday PM peak hours. The traffic modeling and signal timing optimization software package Synchro (Version 10) has been utilized to assess queues at the Project access points. Synchro is a macroscopic traffic software program that is based on the signalized and unsignalized intersection capacity analyses as specified in the HCM. SimTraffic is designed to model networks of signalized and unsignalized intersections, with the primary purpose of checking and fine-tuning signal operations. SimTraffic uses the input parameters from Synchro to generate random simulations. The 95th percentile queue is not necessarily ever observed; it is simply based on statistical calculations (or Average Queue plus 1.65 standard deviations). However, the average queue is the average of all the two-minute maximum queues observed by SimTraffic. The maximum back of queue observed for every two-minute period is recorded by SimTraffic. Many jurisdictions utilize the 95th percentile queues for design purposes.

SimTraffic has been utilized to assess peak hour queuing at the site access driveways for EAPC (2020) traffic conditions. The random simulations generated by SimTraffic have been utilized to determine the 95th percentile queue lengths observed for each turn lane. A SimTraffic simulation has been recorded 5 times, during the weekday AM and weekday PM peak hours, and has been seeded for 30-minute periods with 60-minute recording intervals. Queuing results are provided in Appendix 1.2. Based on the 95th percentile queues under EAPC (2020) traffic conditions, the westbound left turn pocket at Driveway 2 is recommended to accommodate 150-feet of storage.



1.9 TRUCK ACCESS

Exhibit 1-5 illustrates the inbound and outbound truck access for Driveway 2. Due to the typical wide turning radius of these large trucks, a truck turning template has been overlaid on the site plan at Driveway 2, which is anticipated to serve heavy trucks in order to determine appropriate curb radii and to verify that trucks will have sufficient space to execute turning maneuvers. In an effort to provide a conservative assessment of curb radii at each Project driveway, the turning template for a WB-67 class heavy truck has been utilized. It appears that the southwest curb radius at Driveway 2 should accommodate a 75-foot radius (currently showing 50-foot radius) in order to provide sufficient roadway width to accommodate the anticipated ingress of heavy trucks.

1.10 SIGHT DISTANCE ANALYSIS

The intersection stopping sight distance has been evaluated for each Project driveway on Indian Avenue and Ramona Expressway. Sight distance is the continuous length of highway ahead visible to the driver. At unsignalized intersections, intersection sight distance must provide a substantially clear line of sight between the driver of the vehicle waiting on the minor road (driveway) and the driver of an approaching vehicle. Per the American Association of State Highway Transportation Officials (AASHTO), a 7 ½ second criterion has been applied to the outside travel lanes in either direction to provide the most conservative sight distance for the purposes of this analysis. (3) The 7 ½ second criterion allows waiting vehicles to either cross all lanes of through traffic by turning left or cross the near lanes by turning right without requiring through traffic to radically alter their speed. The 7 ½ second criterion is the most conservative measure because it results in sight distances that are greater than all other sight distance requirements.

1.10.1 SIGHT DISTANCE STANDARDS


Ramona Expressway – Ramona Expressway is an existing roadway and the sight distance at the proposed Project driveway (Driveway 1) along Ramona Expressway has been assessed assuming the "object" in the road is another vehicle. Ramona Expressway has been evaluated as an Expressway with a posted speed limit of 55 miles per hour per the County of Riverside's Standard No. 821.


Indian Avenue – Indian Avenue is an existing roadway and the sight distance at the proposed Project driveways along Indian Avenue have been assessed assuming the "object" in the road is another vehicle. Indian Avenue has been evaluated as a Secondary Arterial with a posted speed limit of 40 miles per hour per the County of Riverside's Standard No. 821.

Adequate visibility for vehicular and pedestrian traffic can be provided at each Project driveway by limiting sight obstructions within the limited use area. Any landscaping/hardscape within the limited use area should not exceed 30-inches (2.5-feet) in height, including vegetation. The limited use area should be kept clear of any landscaping or any other obstructions that may impede the visibility of the driver, including on-street parking. Minimum horizontal intersection sight distance for the Project driveways is illustrated on Exhibit 1-6.



EXHIBIT 1-5: TRUCK ACCESS















EXHIBIT 1-6: SIGHT DISTANCE







LEGEND:

= = MINIMUM SIGHT DISTANCE LINES

SERVICE = LIMITED USE AREA

(THERE SHALL BE NO OBSTRUCTION WITHIN THE LIMITED USE AREA. OBSTRUCTIONS INCLUDE, BUT NOT LIMITED TO, ANY SIGNS OR OBJECTS HIGHER THAN 2.5' MEASURED FROM PAVEMENT WITHIN THE AREA OF LIMITED USE.)





SIGHT DISTANCE AT PROJECT DRIVEWAY ALONG RAMONA EXPRESSWAY

The City of Perris does not have standards regarding minimum distances between driveways and intersections; thus, this analysis has been performed using the County of Riverside standards. The County's Standard No. 821 states that the minimum intersection corner sight distance on a roadway with a speed limit of 55 miles per hour is 605-feet. As shown on Exhibit 1-6, it is anticipated that the minimum 605-foot corner sight distance can be accommodated on Ramona Expressway in both the eastbound and westbound directions.

SIGHT DISTANCE AT PROJECT DRIVEWAYS ALONG INDIAN AVENUE

The County's Standard No. 821 states that the minimum intersection corner sight distance on a roadway with a speed limit of 40 miles per hour is 440-feet. As shown on Exhibit 1-6, it is anticipated that the minimum 440-foot corner sight distance can be accommodated on Indian Avenue in both the northbound and southbound directions at Driveways 2 and 3.



This Page Intentionally Left Blank



2 METHODOLOGIES

This section of the report presents the methodologies used to perform the traffic analyses summarized in this report. The methodologies described are generally consistent with City of Perris and the California Department of Transportation (Caltrans) traffic study guidelines. (4)

2.1 LEVEL OF SERVICE

Traffic operations of roadway facilities are described using the term "Level of Service" (LOS). LOS is a qualitative description of traffic flow based on several factors such as speed, travel time, delay, and freedom to maneuver. Six levels are typically defined ranging from LOS A, representing completely free-flow conditions, to LOS F, representing breakdown in flow resulting in stop-and-go conditions. LOS E represents operations at or near capacity, an unstable level where vehicles are operating with the minimum spacing for maintaining uniform flow.

2.2 Intersection Capacity Analysis

The definitions of LOS for interrupted traffic flow (flow restrained by the existence of traffic signals and other traffic control devices) differ slightly depending on the type of traffic control. The LOS is typically dependent on the quality of traffic flow at the intersections along a roadway. The <u>Highway Capacity Manual</u> (HCM) methodology expresses the LOS at an intersection in terms of delay time for the various intersection approaches. (5) The HCM uses different procedures depending on the type of intersection control.

2.2.1 SIGNALIZED INTERSECTIONS

The City of Perris requires signalized intersection operations analysis based on the methodology described in the HCM. (5) Intersection LOS operations are based on an intersection's average control delay. Control delay includes initial deceleration delay, queue move-up time, stopped delay, and final acceleration delay. For signalized intersections, LOS is directly related to the average control delay per vehicle and is correlated to a LOS designation as described in Table 2-1. Study area intersections have been evaluated using the Synchro (Version 10) analysis software package.

Synchro is a macroscopic traffic software program that is based on the signalized intersection capacity analysis as specified in the HCM. Macroscopic level models represent traffic in terms of aggregate measures for each movement at the study intersections. Equations are used to determine measures of effectiveness such as delay and queue length. The level of service and capacity analysis performed by Synchro takes into consideration optimization and coordination of signalized intersections within a network.



TABLE 2-1: SIGNALIZED INTERSECTION LOS THRESHOLDS

Description	Average Control Delay (Seconds), V/C ≤ 1.0	Level of Service, V/C ≤ 1.0	Level of Service, V/C > 1.0
Operations with very low delay occurring with favorable progression and/or short cycle length.	0 to 10.00	А	F
Operations with low delay occurring with good progression and/or short cycle lengths.	10.01 to 20.00	В	F
Operations with average delays resulting from fair progression and/or longer cycle lengths. Individual cycle failures begin to appear.	20.01 to 35.00	С	F
Operations with longer delays due to a combination of unfavorable progression, long cycle lengths, or high V/C ratios. Many vehicles stop and individual cycle failures are noticeable.	35.01 to 55.00	D	F
Operations with high delay values indicating poor progression, long cycle lengths, and high V/C ratios. Individual cycle failures are frequent occurrences. This is considered to be the limit of acceptable delay.	55.01 to 80.00	E	F
Operation with delays unacceptable to most drivers occurring due to over saturation, poor progression, or very long cycle lengths	80.01 and up	F	F

Source: HCM, 6th Edition

The peak hour traffic volumes have been adjusted using a peak hour factor (PHF) to reflect peak 15-minute volumes. Common practice for LOS analysis is to use a peak 15-minute rate of flow. However, flow rates are typically expressed in vehicles per hour. The PHF is the relationship between the peak 15-minute flow rate and the full hourly volume (e.g. PHF = [Hourly Volume] / [4 x Peak 15-minute Flow Rate]). The use of a 15-minute PHF produces a more detailed analysis as compared to analyzing vehicles per hour. Existing PHFs have been used for Existing (2018) baseline, E+P, EA (2020), EAP (2020), EAC (2020) and EAPC (2020) traffic conditions.

2.2.2 UNSIGNALIZED INTERSECTIONS

The City of Perris requires the operations of unsignalized intersections be evaluated using the methodology described the HCM. (5) The LOS rating is based on the weighted average control delay expressed in seconds per vehicle (see Table 2-2).

TABLE 2-2: UNSIGNALIZED INTERSECTION LOS THRESHOLDS

Description	Average Control Delay Per Vehicle (Seconds)	Level of Service, V/C ≤ 1.0	Level of Service, V/C > 1.0
Little or no delays.	0 to 10.00	Α	F
Short traffic delays.	10.01 to 15.00	В	F
Average traffic delays.	15.01 to 25.00	С	F
Long traffic delays.	25.01 to 35.00	D	F
Very long traffic delays.	35.01 to 50.00	E	F
Extreme traffic delays with intersection capacity exceeded.	> 50.00	F	F

Source: HCM, 6th Edition



At two-way or side-street stop-controlled intersections, LOS is calculated for each controlled movement and for the left turn movement from the major street, as well as for the intersection as a whole. For approaches composed of a single lane, the delay is computed as the average of all movements in that lane. For all-way stop controlled intersections, LOS is computed for the intersection as a whole.

2.3 TRAFFIC SIGNAL WARRANT ANALYSIS METHODOLOGY

The term "signal warrants" refers to the list of established criteria used by the Caltrans and other public agencies to quantitatively justify or ascertain the potential need for installation of a traffic signal at an otherwise unsignalized intersection. This TIA uses the signal warrant criteria presented in the latest edition of the Caltrans <u>California Manual on Uniform Traffic Control Devices</u> (CA MUTCD) for all study area intersections. (6)

The signal warrant criteria for Existing conditions are based upon several factors, including volume of vehicular and pedestrian traffic, frequency of accidents, and location of school areas. The Caltrans <u>CA MUTCD</u> indicates that the installation of a traffic signal should be considered if one or more of the signal warrants are met. (6) Specifically, this TIA utilizes the Peak Hour Volume-based Warrant 3 as the appropriate representative traffic signal warrant analysis for existing study area intersections for all analysis scenarios. Warrant 3 is appropriate to use for this TIA because it provides specialized warrant criteria for intersections with rural characteristics (e.g. located in communities with populations of less than 10,000 persons or with adjacent major streets operating above 40 miles per hour). For the purposes of this study, the speed limit was the basis for determining whether Urban or Rural warrants were used for a given intersection.

Future intersections that do not currently exist have been assessed regarding the potential need for new traffic signals based on future average daily traffic (ADT) volumes, using the Caltrans planning level ADT-based signal warrant analysis worksheets.

Traffic signal warrant analyses were performed for the following study area intersection shown in Table 2-3:

TABLE 2-3: TRAFFIC SIGNAL WARRANT ANALYSIS LOCATIONS

ID	Intersection Location	Jurisdiction
2	Driveway 2 & Indian Street	City of Perris

The Existing conditions traffic signal warrant analysis is presented in the subsequent section, Section 3 *Area Conditions* of this report. The traffic signal warrant analyses for future conditions are presented in Section 5 *E+P Traffic Analysis*, Section 6 *EA and EAP (2020) Traffic Analysis*, and Section 7 *EAC and EAPC (2020) Traffic Analysis* of this report.

It is important to note that a signal warrant defines the minimum condition under which the installation of a traffic signal might be warranted. Meeting this threshold condition does not require that a traffic control signal be installed at a particular location, but rather, that other traffic factors and conditions be evaluated in order to determine whether the signal is truly justified. It should also be noted that signal warrants do not necessarily correlate with LOS. An



intersection may satisfy a signal warrant condition and operate at or above acceptable LOS or operate below acceptable LOS and not meet a signal warrant.

2.4 MINIMUM LEVEL OF SERVICE (LOS)

The definition of an intersection deficiency has been obtained from the City of Perris' General Plan:

LOS D along all City maintained roads (including intersections) and LOS D along I-215 and SR-74 (including intersections with local streets and roads). An exception to the local road standard is LOS E, at intersections of any Arterials and Expressways with SR-74, the Ramona-Cajalco Expressway, or at I-215 Freeway ramps. (7)

LOS E may be allowed within the boundaries of the Downtown Specific Plan Area to the extent that it would support transit-oriented development and walkable communities. Increased congestion in this area will facilitate an increase in transit ridership and encourage development of a complementary mix of land uses within a comfortable walking distance from light rail stations.

2.5 CEQA COMPLIANCE AND DOCUMENTATION

This section outlines the methodology used in this analysis related to identifying circulation system deficiencies.

For purposes of analyzing California Environmental Quality Act (CEQA) impacts, the analysis shall evaluate significant impacts based on the following criteria to determine whether the addition of project-generated trips (or alternative-generated trips) results in a significant impact, and thus requires mitigation:

- A project-related impact is considered direct and significant when a study intersection operates
 at an acceptable LOS for existing conditions (without the project) and the addition of 50 or more
 AM or PM peak hour project trips causes the intersection to operate at an unacceptable LOS for
 existing plus project (E+P) traffic conditions.
- A project-related impact is considered direct and significant when a study intersection operates
 at an unacceptable LOS for existing conditions (without the project) and the addition of 50 or
 more AM or PM peak hour project trips causes the intersection delay to increase by 2 seconds or
 more.
- A cumulative impact is considered significant when a study intersection is forecast to operate at an unacceptable LOS with the addition of cumulative/background traffic and 50 or more AM or PM peak hour project trips.

2.6 SB 743 REQUIREMENTS

In the fall of 2013, Senate Bill 743 (SB 743) was passed by the legislature and signed into law by the governor. For some parts of California (and possibly the entire State), this legislation will eventually change the way that transportation studies are conducted for environmental documents. In the areas where SB 743 is implemented, delay-based metrics such as roadway



capacity and level of service will no longer be the performance measures used for the determination of the transportation impacts of projects in studies conducted under CEQA. Instead, new performance measures such as vehicle miles travelled (VMT) or other similar measures will be used.

During the preparation of this traffic impact study, guidelines for the implementation of SB 743 were still being written and this legislation was not yet incorporated into CEQA. Therefore, this traffic impact study follows current practice regarding state and local guidance as of the date of preparation. Depending on the schedule for implementation of SB 743 and the schedule for preparation of the environmental document for this project, additional studies may need to be considered to fully incorporate SB 743.

It should be noted that the Project is not subject to SB 743 as of the date of preparation of this traffic study.



This Page Intentionally Left Blank



3 AREA CONDITIONS

This section provides a summary of the existing circulation network, the City of Perris General Plan Circulation Network, and a review of existing peak hour intersection operations and traffic signal warrant analyses.

3.1 EXISTING CIRCULATION NETWORK

Pursuant to the scoping agreement with City of Perris staff (Appendix 1.1), the study area includes a total of 4 existing and future intersections as shown previously on Exhibit 1-2 where the Project is anticipated to contribute 50 or more peak hour trips. Exhibit 3-1 illustrates the study area intersections located near the proposed Project and identifies the number of through traffic lanes for existing roadways and intersection traffic controls.

3.2 GENERAL PLAN CIRCULATION ELEMENTS

As noted previously, the Project site is located within PVCC SP in the City of Perris. Exhibit 3-2 shows the City of Perris General Plan Circulation Element, and Exhibit 3-3 illustrates the City of Perris General Plan roadway cross-sections. Exhibit 3-4 illustrates the PVCC SP Circulation Plan and Exhibit 3-5 shows the corresponding PVCC SP roadway cross-sections.

3.3 TRUCK ROUTES

The City of Perris designated truck route map is shown on Exhibit 3-6. Harley Knox Boulevard and Indian Avenue are identified as designated truck routes. Although the City's truck route map identifies Ramona Expressway as a designated truck route, the PVCC SP truck route plan and the City's current direction is to prohibit trucks along Ramona Expressway. The PVCC SP truck route plan is shown on Exhibit 3-7. Consistent with the City of Perris designated truck route map, Harley Knox Boulevard and Indian Avenue are identified as designated truck routes within the PVCC SP. These designated truck route maps have been utilized to route truck traffic from future cumulative development projects throughout the study area. It should be noted that the City of Perris City Council's policy is for trucks to utilize the Harley Knox Boulevard interchange within this study area and not have any trucks on Ramona Expressway. As such, Project truck traffic will also be routed to the north to the Harley Knox Boulevard interchange via Indian Avenue.


3.4 Transit Service

The study area is currently served by the Riverside Transit Authority (RTA), a public transit agency serving the Riverside County region (see Exhibit 3-8). Mass transit routes within the PVCC SP are shown on Exhibit 3-9. Exhibit 3-9 also shows future potential routes along Ramona Expressway. As shown on Exhibit 3-8 and Exhibit 3-9, the existing RTA Route 19 (Alternative) and RTA Route 41 could potentially serve the proposed Project.



2U PERRY ST. 2 SITE DWY. 3 (P) (RIRO) 3 * INDIAN AV DWY 1. (P) (RIRO) 0 **7D** 4 6D RAMONA EXWY.

EXHIBIT 3-1: EXISTING NUMBER OF THROUGH LANES AND INTERSECTION CONTROLS









= NUMBER OF LANES

= DIVIDED

= UNDIVIDED

= SPEED LIMIT (MPH)





SITE EGEND Perris City Limits 215 Freeway MOUNTAIN AVE 74 Expressway (184' ROW) APES RD Primary Arterial (128' ROW) Secondary Arterial (94' ROW) Major Collector (78' ROW) Collector (66' ROW) Corridor Study Area Proposed Interchange Existing Interchange to be Modified Source: City of Perris General Plan, 2005, As Amended Riverside Co.


EXHIBIT 3-2: CITY OF PERRIS GENERAL PLAN CIRCULATION ELEMENT

11704 - perris-ce.dwg

EXHIBIT 3-3: CITY OF PERRIS GENERAL PLAN ROADWAY CROSS-SECTIONS







Legend

- (1) No stopping any time both sides.
- * The width of the collector street can range from 40 feet to 64 feet curb-to-curb.
- (2) Bike lane where designated.

TWLTL = Two Way Left Turn Lane

Source: City of Perris General Plan 8-2008



LEGEND SPECIFIC PLAN BOUNDARY **EXPRESSWAY** = ARTERIAL SECONDARY ARTERIAL COLLECTOR = LOCAL NANDINA AVE TRUCK ROUTE P. V. STORM CHANNEL R.C.F.C.D. Channe HARLEY_KNOX_BLVD NANCE ST NDIAN SON MARKHAM ST PERRI TON AV SITE ** BLV DAWES ST MORGAN_ST RIDER-ST MILSON Source: PVCC SP City of Perris 05-2018

EXHIBIT 3-4: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN CIRCULATION PLAN







EXHIBIT 3-5: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN CROSS-SECTIONS





SITE Note: Ramona MORGAN ST Expressway is no longer a truck route. RIDER ST PLACENTIA AVE ORANGE AVE METZ RD SAN JACINTO AVE ELLIS AVE MURRIETA RD MAPES RD **LEGEND** Truck Routes Perris City Limits Source: City of Perris General Plan 08-26-2008

EXHIBIT 3-6: CITY OF PERRIS TRUCK ROUTES





EXHIBIT 3-7: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN TRUCK ROUTE PLAN




EXHIBIT 3-8: EXISTING TRANSIT ROUTES





= RTA ROUTE 41

■■■ = RTA ROUTE 19 (ALTERNATIVE)





LEGEND SPECIFIC PLAN BOUNDARY EXISTING/POTENTIAL STOP TRANSFER POINT METROLINK STATION (PROPOSED) NANDINA AVE **BUS ROUTE 19 BUS ROUTE 19 ALTERNATE** × **BUS ROUTE 41** POTENTIAL ROUTE R.C.F.C.D. Channel HARLEY KNOX BLVD TERSON AV NANCE ST MARKHAM ST BLV SITE AMONAEXPRESSW DAWES ST MORGAN ST WEBSTER INDIAN SINCLAIR ST RIDER ST MILSON ACENTIA ST Source: PVCC SP City of Perris 05-2018

EXHIBIT 3-9: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN MASS TRANSIT ROUTES



Transit service is reviewed and updated by RTA periodically to address ridership, budget and community demand needs. Changes in land use can affect these periodic adjustments which may lead to either enhanced or reduced service where appropriate. Consistent with MM Trans 4 of the PVCC SP EIR, the Project will submit a plan to RTA to review and provide comments on bus stops and turnouts prior to Project approval.

3.5 BICYCLE & PEDESTRIAN FACILITIES

In an effort to promote alternative modes of transportation, the City of Perris also includes a proposed bikeways and trail system. The City of Perris proposed bikeways and trail system is shown on Exhibit 3-10. Ramona Expressway and Indian Avenue are proposed to have Class II bike lanes. PVCC SP Trail System is shown on Exhibit 3-11. As shown, there is a regional trail planned along Ramona Expressway. Field observations conducted in May 2018 indicate nominal pedestrian and bicycle activity within the study area. Exhibit 3-12 illustrates the existing bicycle and pedestrian facilities, including bike lanes, sidewalks and crosswalk locations.

3.6 EXISTING TRAFFIC COUNTS

The intersection LOS analysis is based on the traffic volumes observed during the peak hour conditions using traffic count data collected in May 2018, while schools were in session. The following peak hours were selected for analysis:

- Weekday AM Peak Hour (peak hour between 7:00 AM and 9:00 AM)
- Weekday PM Peak Hour (peak hour between 4:00 PM and 6:00 PM)

The weekday AM and weekday PM peak hour count data is representative of typical weekday peak hour traffic conditions in the study area. There were no observations made in the field that would indicate atypical traffic conditions on the count dates, such as construction activity or detour routes and near-by schools were in session and operating on normal schedules.

The raw manual peak hour turning movement traffic count data sheets are included in Appendix 3.1. These raw turning volumes have been flow conserved between intersections with limited access, no access, and where there are currently no uses generating traffic. The traffic counts collected in May 2018 include the vehicle classifications as shown below:

- Passenger Cars
- 2-Axle Trucks
- 3-Axle Trucks
- 4 or More Axle Trucks



B1 (65) ್ಜಿ @ Legend @ (d) Proposed Class II Mid County Parkway City Preferred Alignn (40)


EXHIBIT 3-10: CITY OF PERRIS PROPOSED BIKEWAYS AND TRAIL IMPROVEMENTS

Source: City of Perris General Plan





EXHIBIT 3-11: PERRIS VALLEY COMMERCE CENTER SPECIFIC PLAN TRAIL SYSTEM







PERRY ST. 2 SITE DWY. 3 (P) (RIRO) 3 (1)

EXHIBIT 3-12: EXISTING PEDESTRIAN FACILITIES



RAMONA EXWY.



= SIDEWALK



NO CROSSWALKFUTURE INTERSECTION



- CROSSWALK ON ALL APPROACHES



To represent the impact large trucks, buses, and recreational vehicles have on traffic flow, all trucks were converted into PCEs. By their size alone, these vehicles occupy the same space as two or more passenger cars. In addition, the time it takes for them to accelerate and slow-down is also much longer than for passenger cars and varies depending on the type of vehicle and number of axles. For this analysis, a PCE factor of 1.5 has been applied to 2-axle trucks, 2.0 for 3-axle trucks, and 3.0 for 4+-axle trucks to estimate each turning movement. These factors are consistent with the values recommended for use in the San Bernardino County CMP and are in excess of the factor recommended for use in the County of Riverside traffic study guidelines. (8) Although the County of Riverside has a recommended PCE factor of 2.0, the San Bernardino County CMP PCE factors have been utilized in an effort to conduct a more conservative analysis.

Existing weekday average daily traffic (ADT) volumes on arterial highways throughout the study area are shown on Exhibit 3-13. Where actual 24-hour tube count data was not available, Existing ADT volumes were based upon factored intersection peak hour counts collected by Urban Crossroads, Inc. using the following formula for each intersection leg:

Weekday PM Peak Hour (Approach Volume + Exit Volume) x 17.1389 = Leg Volume

A comparison of the PM peak hour and daily traffic volumes of various roadway segments within the study area indicated that the peak-to-daily relationship is approximately 5.84 percent. As such, the above equation utilizing a factor of 17.1389 estimates the ADT volumes on the study area roadway segments assuming a peak-to-daily relationship of approximately 5.84 percent (i.e., 1/0.0584 = 17.1389) and was assumed to sufficiently estimate average daily traffic (ADT) volumes for planning-level analyses. Existing weekday AM and weekday PM peak hour intersection volumes (in PCE) are also shown on Exhibit 3-13.

3.7 Intersection Operations Analysis

Existing peak hour traffic operations have been evaluated for the study area intersections based on the analysis methodologies presented in Section 2.2 *Intersection Capacity Analysis* of this report. The intersection operations analysis results are summarized in Table 3-1 which indicates that the study area intersections are currently operating at an acceptable LOS during the peak hours (i.e., LOS B or better).

Consistent with Table 3-1, a summary of the peak hour intersection LOS for Existing conditions are shown on Exhibit 3-14. The intersection operations analysis worksheets are included in Appendix 3.2 of this TIA.


3.8 Traffic Signal Warrants Analysis

No traffic signal warrant analysis has been performed for Existing (2018) traffic conditions as the only unsignalized intersection is currently restricted to right-in/right-out access only.



0.2 PERRY ST. SITE DWY. 3 (P) (RIRO) 3 * NDIAN AV DWY 1. (P) (RIRO) 0 4 46.0 RAMONA EXWY. Dwy. 1 & 2 Ramona Exwy. Indian Av. & 3 Dwy. 2 / Perry St. Indian Av. & 4 Dwy. 3 Indian Av. & 1 Ramona Exwy.

EXHIBIT 3-13: EXISTING (2018) TRAFFIC VOLUMES (IN PCE)



10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES

10.0 = ACTUAL (COUNT-BASED) VEHICLES PER DAY (1000'S)

10.0 - ESTIMATED VEHICLES PER DAY (1000'S)



PERRY ST. SITE DWY. 3 (P) (NA) * (RIRO) **DWY 1. (P)** NDIAN AV. (RIRO) (NA) **LEGEND:** RAMONA EXWY. - AM PEAK HOUR **PM PEAK HOUR** - LOS A-D - LOS E - LOS F - NOT AN ANALYSIS LOCATION FOR THIS SCENARIO

EXHIBIT 3-14: EXISTING (2018) SUMMARY OF LOS



Table 3-1

Intersection Analysis for Existing (2018) Conditions

						İr	nters	ectio	n Ap	pro	ach L	ane:	s¹			Del	Delay ² L		el of
			Traffic	Nor	Northbound Southbound				Eas	stbou	ınd	We	stbo	und	(se	cs.)	Ser	vice	
:	#	Intersection	Control ³	L	Т	R		Т	R	L	Т	R	L	Т	R	AM	PM	AM	PM
	1	Driveway 1 & Ramona Expressway		Future Intersection															
	2	Indian Avenue & Driveway 2/Perry Street	CSS	0	2	0	0	2	0	0	0	1	0	0	1	9.6	9.1	Α	Α
	3	Indian Avenue & Driveway 3						Futur	e Int	erse	ection	1							
	4	Indian Avenue & Ramona Expressway	TS	1	2	0	1	2	1	1	3	0	1	3	1	19.1	19.7	В	В

When a right turn is designated, the lane can either be striped or unstriped. To function as a right turn lane there must be sufficient width for right turning vehicles to travel outside the through lanes.

L = Left; T = Through; R = Right



² Per the Highway Capacity Manual (HCM) (6th Edition), overall average intersection delay and level of service are shown for intersections with a traffic signal or all way stop control. For intersections with cross street stop control, the delay and level of service for the worst individual movement (or movements sharing a single lane) are shown.

³ TS = Traffic Signal; CSS = Cross-Street Stop

4 PROJECTED FUTURE TRAFFIC

This section presents the traffic volumes estimated to be generated by the Project, as well as the Project's trip assignment, onto the study area roadway network. The Project is proposed to consist of a single high-cube transload and short-term storage warehouse building at approximately 428,730 sf. The Project is anticipated to be constructed in a single phase by the year 2020. The proposed Project land use is consistent with PVCC SP. The designated land use and zoning within the PVCCP SP is Light Industrial within the APZI and APZ II overlay. The Project is located within APZ I and APZ II within Zone B1 and is limited to 25 people per acre in the APZI and limited to 50 people per acre in the APZII. The northern portion of the Project site, where parking and access is proposed, is within APZI while the southern portion of the site, where the warehouse building, parking, and access are proposed, is within APZII.

Vehicular and truck traffic access will be provided via the following driveways:

- Driveway 1 & Ramona Expressway Right-in/right-out access only for passenger cars
- Indian Avenue & Driveway 2/Perry Street Full access only for trucks
- Indian Avenue & Driveway 3 Right-in/right-out access only for passenger cars

Regional access to the Project site is provided via the I-215 Freeway and Ramona Expressway for passenger cars and at Harley Knox Boulevard for heavy trucks.

4.1 PROJECT TRIP GENERATION

Trip generation represents the amount of traffic that is attracted and produced by a development, and is based upon the specific land uses planned for a given project. Trip generation rates for the Project are shown in Table 4-1 together with the PCE trip generation summary illustrating daily and peak hour trip generation estimates based on the Institute of Transportation Engineers (ITE) <u>Trip Generation Manual</u>, 10th Edition, 2017, for High-Cube Transload and Short-Term Storage Warehouse (ITE Land Use Code 154). (1)

Data regarding the truck percentage and vehicle mix has been obtained from <u>High Cube Warehouse Vehicle Trip Generation Analysis</u> (October 2016). (9) The <u>High Cube Warehouse Vehicle Trip Generation Analysis</u> provides vehicle mix for Short-Term Storage, Transload & Non-Cold Storage, which consists of 32.2% trucks for daily trips, 30.8% trucks for AM peak hour trips and 21.7% trucks for PM peak hour trips. The South Coast Air Quality Management District's (SCAQMD) recommended truck mix, by axle type for high-cube warehouses has been utilized for the 2-axle, 3-axle, and 4+-axle trucks.



Table 4-1

Project Trip Generation Rates

		ITE LU	AN	И Peak Ho	our	PN	/I Peak Ho	our	Daily
Land Use ¹	Units ²	Code	In	Out	Total	In	Out	Total	Daily
Α	ctual Ve	hicle Tri	p Genera	tion Rate	S				
High-Cube Transload and Short-Term Storage Warehouse (Without Cold Storage) ³	TSF	154	0.062	0.018	0.080	0.028	0.072	0.100	1.400
Passenger Cars (AM-69.2%; PM-78.3	%; Daily	·-67.8%)	0.043	0.013	0.055	0.022	0.056	0.078	0.949
2-Axle Trucks (AM-5.14%; PM-3.62	%; Daily	·-5.38%)	0.003	0.001	0.004	0.001	0.003	0.004	0.075
3-Axle Trucks (AM-6.38%; PM-4.49	%; Daily	·-6.67%)	0.004	0.001	0.005	0.001	0.003	0.004	0.093
4-Axle+ Trucks (AM-19.25%; PM-13.56%	6; Daily-	20.13%)	0.012	0.004	0.015	0.004	0.010	0.014	0.282
Passenger	Car Equ	ivalent (PCE) Trip	Generati	on Rates ⁵				
High-Cube Transload and Short-Term Storage Warehouse (Without Cold Storage) ³	TSF	154	0.062	0.018	0.080	0.028	0.072	0.100	1.400
Passenger Cars (AM-69.2%; PM-78.3	3%; Daily	·-67.8%)	0.043	0.013	0.055	0.022	0.056	0.078	0.949
2-Axle Trucks (AM-5.14%; PM-3.62%; Daily-5.	38%) (PC	CE = 1.5)	0.005	0.001	0.006	0.002	0.004	0.005	0.113
3-Axle Trucks (AM-6.38%; PM-4.49%; Daily-6.				0.002	0.010	0.003	0.006	0.009	0.187
Axle+ Trucks (AM-19.25%; PM-13.56%; Daily-20.:	13%) (PC	CE = 3.0)	0.036	0.011	0.046	0.011	0.029	0.041	0.845

¹ Trip Generation Source: Institute of Transportation Engineers (ITE), Trip Generation Manual, Tenth Edition (2017).

Truck Mix: South Coast Air Quality Management District's (SCAQMD) recommended truck mix, by axle type for high-cube warehouse. PCE rates are per SBCTA.



² TSF = thousand square feet

³ Vehicle Mix Source: <u>High Cube Warehouse Vehicle Trip Generation Analysis</u> October 2016, ITE.

As noted in Table 4-1 and Table 4-2, refinements to the raw trip generation estimates have been made to provide a more detailed breakdown of trips between passenger cars and trucks. Trip generation for heavy trucks was further broken down by truck type (or axle type). The total truck percentage is comprised of 3 different truck types: 2-axle, 3-axle, and 4+-axle trucks. PCE factors were applied to the trip generation rates for heavy trucks (large 2-axles, 3-axles, 4+-axles). PCEs allow the typical "real-world" mix of vehicle types to be represented as a single, standardized unit, such as the passenger car, to be used for the purposes of capacity and level of service analyses. The PCE factors are consistent with the recommended PCE factors in Appendix B of the San Bernardino County Congestion Management Program (CMP), 2016 Update. (8) Note that these procedures are consistent with those adopted by the County of Riverside for warehouse projects, with the exception of the PCE factors, where the San Bernardino County CMP factors have been utilized in an effort to conduct a conservative analysis. The County of Riverside utilizes a default PCE factor of 2.0 for all trucks, whereas, the County of San Bernardino CMP factors are broken down by axle type (1.5 for 2-axle, 2.0 for 3-axle, and 3.0 for 4+-axle). Since there are more 4+-axle trucks than 2-axle and 3-axle trucks, the San Bernardino CMP factors are more conservative because they account for additional PCE (3.0) compared to that of the Riverside factors (2.0). The number of trucks by axle type can be found in Appendix 3.1.

The proposed Project is anticipated to generate a net total of approximately 897 PCE trip-ends per day with 50 PCE AM peak hour trips and 58 PCE PM peak hour trips, as shown in Table 4-2. The proposed Project's trip generation, based on actual vehicles, has also been included in Table 4-2 for informational purposes only.

4.2 PROJECT TRIP DISTRIBUTION

Trip distribution is the process of identifying the probable destinations, directions, or traffic routes that will be utilized by Project traffic. The potential interaction between the planned land uses and surrounding regional access routes are considered to identify the route where the Project traffic would distribute.

The Project trip distribution was developed based on anticipated travel patterns to and from the Project site for both passenger cars and truck traffic, and are consistent with other similar projects that have been reviewed and approved by City of Perris staff. The truck trip distribution patterns have been developed based on the anticipated travel patterns for the warehousing trucks. The Project trip distribution patterns for both passenger cars and trucks were developed based on an understanding of existing travel patterns in the area, the geographical location of the site, and the site's proximity to the regional arterial and state highway system.

The Project passenger car trip distribution pattern is graphically depicted on Exhibit 4-1. The Project truck trip distribution pattern is graphically depicted on Exhibit 4-2. Each of these distribution patterns was reviewed and approved by the City of Perris as part of the traffic study scoping process (see Appendix 1.1).



Table 4-2


Project Trip Generation Summary

			AN	1 Peak H	our	PM	Peak H	our	
Land Use	Quantity	Units⁺	In	Out	Total	In	Out	Total	Daily
Project Trip	Generation S	Summary	(Actual	Vehicles)				
High-Cube Warehouse (Without Cold Storage)	428.730	TSF							
Passenger Cars:			18	5	2 3	9	24	33	407
Truck Trips:									
2-axle:			1	0	1	0	1	1	32
3-axle:			2	1	3	1	1	2	40
4+-axle:			5	2	7	2	4	6	121
- Net Truck Trips (Actual Vehicles)			8	3	11	3	6	9	193
Total Proposed Project (Actual Vel			26	8	34	12	30	42	600
Projec	t Trip Genera	ation Sum	mary (P	CE)					
High-Cube Warehouse (Without Cold Storage)	428.730	TSF							
Passenger Cars:			18	5	2 3	9	24	33	407
Truck Trips:									
2-axle:			2	1	3	1	2	3	48
3-axle:			3	1	4	1	3	4	80
4+-axle:			15	5	20	5	13	18	362
- Net Truck Trips (PCE)			20	7	27	7	18	25	490
Total P	roposed Proj	ect (PCE)	38	12	50	16	42	58	897

¹ TSF = thousand square feet



EXHIBIT 4-1: PROJECT (PASSENGER CAR) TRIP DISTRIBUTION



- 10 = PERCENT TO/FROM PROJECT
- OUTBOUND
- → -- = INBOUND





EXHIBIT 4-2: PROJECT (TRUCKS) TRIP DISTRIBUTION



10 - PERCENT TO/FROM PROJECT





4.3 MODAL SPLIT

The traffic reducing potential of public transit, walking, or bicycling have not been considered in this TIA. Essentially, the traffic projections are "conservative" in that these alternative travel modes might be able to reduce the forecasted traffic volumes (employee trips only).

4.4 PROJECT TRIP ASSIGNMENT

The assignment of traffic from the Project area to the adjoining roadway system is based upon the Project trip generation, trip distribution, and the arterial highway and local street system improvements that would be in place by the time of initial occupancy of the Project. Based on the identified Project traffic generation and trip distribution patterns, Project ADT and peak hour intersection turning movement volumes are shown on Exhibit 4-3 in PCE.

4.5 BACKGROUND TRAFFIC

Future year traffic forecasts have been based upon two years of background (ambient) growth at 3% per year, compounded over 2 years, for 2020 traffic conditions. The total ambient growth is 6.09% for 2020 traffic conditions (compounded growth of 3 percent per year, compounded over two years or $1.03^{2 \text{ years}}$). This ambient growth rate is added to existing traffic volumes to account for area-wide growth not reflected by cumulative development projects. Ambient growth has been added to daily and peak hour traffic volumes on surrounding roadways, in addition to traffic generated by the development of future projects that have been approved but not yet built and/or for which development applications have been filed and are under consideration by governing agencies.

The Southern California Association of Governments (SCAG) 2016—2040 Regional Transportation Plan/Sustainable Communities Strategy (RTP/SCS) growth forecasts for the City of Perris assume the City population to increase from 70,700 in 2012 to 116,700 by the year 2040, or an approximate 1.81 percent growth rate compounded annually. The RTP/SCS assumed growth in households over the same 28-year period reflects an increase from 16,600 households to 32,700 households; a rate of 2.45 percent compounded annually. At the upper end of assumed RTP/SCS growth rates, employment over the same 28-year period is projected to increase from 15,100 jobs to 32,200 jobs; a rate of approximately 2.74 percent compounded annually. (10)

Therefore, the use of an annual growth rate of 3.0 percent would appear to conservatively approximate the anticipated regional growth in traffic volumes in the City of Perris, especially when considered along with the addition of Project-related traffic and traffic generated by other known development projects. As such, the growth in traffic volumes assumed in this traffic impact analysis would tend to overstate as opposed to understate the potential impacts to traffic and circulation.



PERRY ST. 2 DWY. 2 (T) (FULL) CEQA STUDY AREA DWY. 3 (P) (RIRO) 0.1 **DWY 1. (P)** INDIAN AV. (RIRO) 0.3 (\mathbf{I}) RAMONA EXWY.

EXHIBIT 4-3: PROJECT ONLY TRAFFIC VOLUMES (IN PCE)

1	Dwy. 1 & Ramona Exwy.		Indian Av. & . 2 / Perry St.	3	Indian Av. & Dwy. 3	4	Indian Av. & ≀amona Exwy.
	9(5)→ 9(5)→	7(18) 7(18) 7(18) 7(18) 7(18) 7(18) 7(19)	0(0) +0(0) +0(0) -0(0) 1 (0) 000	(0)0→ (E)5→ 1(5)	← (0)0	0(0) 0(0) 0(0) 0(1) 0(1) 0(1)	(0)0 +-3(1) 0(0) 1 (0)0 1 (0)0

10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES

10.0 - VEHICLES PER DAY (1000'S)

NOM - NOMINAL, LESS THAN 50 VEHICLES PER DAY



4.6 CUMULATIVE DEVELOPMENT TRAFFIC

California Environmental Quality Act (CEQA) guidelines require that other reasonably foreseeable development projects which are either approved or being processed concurrently in the study area also be included as part of a cumulative analysis scenario. A cumulative project list was developed for the purposes of this analysis through consultation with planning and engineering staff from the City of Perris. The cumulative project list includes known and foreseeable projects that are anticipated to contribute traffic to the study area intersections. Adjacent jurisdictions of the County of Riverside and the City of Moreno Valley have also been contacted to obtain the most current list of cumulative projects from their respective jurisdictions.

Where applicable, cumulative projects anticipated to contribute measurable traffic (i.e. 50 or more peak hour trips) to study area intersections have been manually added to the study area network to generate EAC and EAPC forecasts. In other words, this list of cumulative development projects has been reviewed to determine which projects would likely contribute measurable traffic through the study area intersections (e.g., those cumulative projects in close proximity to the proposed Project). For the purposes of this analysis, the cumulative projects that were determined to affect one or more of the study area intersections are shown on Exhibit 4-4, listed in Table 4-3, and have been considered for inclusion.

Although it is unlikely that these cumulative projects would be fully built and occupied by Year 2020, they have been included in an effort to conduct a conservative analysis and overstate as opposed to understate potential traffic impacts.

Any other cumulative projects that are not expected to contribute measurable traffic to study area intersections have not been included since the traffic would dissipate due to the distance from the Project site and study area intersections. Any additional traffic generated by other projects not on the cumulative projects list is accounted for through background ambient growth factors that have been applied to the peak hour volumes at study area intersections as discussed in Section 4.5 *Background Traffic*. Cumulative Only ADT and peak hour intersection turning movement volumes are shown on Exhibit 4-5 in PCE.


4.7 TRAFFIC FORECASTS

An E+P analysis scenario has been included to address a recent CEQA case ruling, which asserts that impacts of a proposed project must be measured against the current existing physical conditions.

To provide a comprehensive assessment of potential transportation network deficiencies, two types of analyses, "buildup" and "buildout", were performed in support of this work effort. The buildup method was utilized to approximate the EA/EAP and EAC/EAPC conditions for the analysis year of 2020, and is intended to identify the near-term cumulative impacts on both the existing and planned near-term circulation system. The EA/EAP traffic condition includes background traffic and the traffic generated by the proposed Project. The EAC/EAPC traffic condition includes traffic generated by other cumulative development projects within the study area in addition to the background traffic and traffic generated by the proposed Project.




EXHIBIT 4-4: CUMULATIVE DEVELOPMENT LOCATION MAP



PERRY ST. SITE DWY. 3 (P) (RIRO) 3 * NDIAN AV DWY 1. (P) (RIRO) 0 8.8 4 RAMONA EXWY.

EXHIBIT 4-5: CUMULATIVE ONLY TRAFFIC VOLUMES (IN PCE)



10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES

10.0 - VEHICLES PER DAY (1000'S)

NOM = NOMINAL, LESS THAN 50 VEHICLES PER DAY





Table 4-3 Page 1 of 2

Cumulative Development Land Use Summary

WEST OF WEBSTER AVE. NORTH OF RAMONA Exwy. SOUTH OF HARLEY KNOX BLVD. EAST OF HWY. 215 WEST OF WEBSTER AVE. NORTH OF MARKHAM ST. NWC OF HARLEY KNOX BLVD. & REDLANDS AVE. EAST OF WEBSTER AVE. SOUTH OF NANCE ST. NWC OF REDLANDS AVE. AND NANCE AVE. NORTH OF RIDER ST. WEST OF REDLANDS SEC OF PATTERSON AVE. & MARKHAM ST. WEST OF PERRIS BLVD. AT AVOCADO AVE. SWC OF REDLANDS AVE. & MARKHAM ST. NORTH OF RIDER ST. EAST OF REDLANDS NEC OF INDIAN AVE. & MARKHAM ST. WEST OF EVANS RD. AT MARKHAM ST. SWC OF REDLANDS AVE. & PERRY ST. WEST OF EVANS RD. AT CITRUS AVE. SWC OF REDLANDS AVE. & RIDER ST. NWC OF INDIAN AVE. & RIDER ST. SWC OF INDIAN ST. & NANCE ST. **NEC OF INDIAN & MARKHAM NEC OF WEBSTER & NANCE** Units TSF 2 2 386.278 270 173.000 669.000 240.000 400.000 864.000 1,455.000 1,037.000 460.000 170.000 1,200.000 350.000 1,376.721 640.000 180.000 811.000 520.000 496 210.900 Quantity High-Cube Warehouse Commercial Retail Land Use Warehousing Warehousing Warehousing Warehousing SFDR SFDR Jurisdiction Perris Harley Knox Commerce Park / DPR 16-004 Stratford Ranch Residential / TTM 36648 Markham Industrial / DPR 16-00015 Westcoast Textile / DPR 16-00001 Duke at Patterson / DPR 17-00001 Perris Marketplace / DPR 05-0341 Pulte Residential / TTM 30850 Bargemann / DPR 07-09-0018 Project Name / Case Number Markham East / DPR 05-0477 First Perry / DPR 16-00013 Gateway / DPR 16-00003 Integra / DPR 14-02-0014 OLC 1 / DPR 12-10-0005 OLC2 / DPR 14-01-0015 Duke 2 / DPR 16-00008 Rider 1 / DPR 16-0365 Rider 3 / DPR 06-0432 Rados / DPR 07-0119 Perris Circle 3 Rider 2 & 4 P20 P10 P12 P15 P16 P18 P14 P11 P13 P17 P19 Ь3 **P**4 P5 **9**6 8 8 P9 P2 Ы P_1

Table 4-3 Page 2 of 2

Cumulative Development Land Use Summary

Š	Project Name / Case Number	Iurisdiction	Land Use ¹	Ouantity	Units ²	Location
MV1	Kearney	Moreno Valley	High-Cube Warehouse	1100.000	TSF	EAST OF PERRIS BLVD. AT SAN MICHEL RD.
MV2	SOI	Moreno Valley	High-Cube Warehouse	701.000	TSF	SEC OF HEACOCK ST. & SAN MICHELE RD.
MV3	First Industrial	Moreno Valley	High-Cube Warehouse	1380.000	TSF	SWC OF INDIAN AVE. & NANDINA AVE.
MV4	Prologis 1	Moreno Valley	High-Cube Warehouse	1000.000	TSF	NEC OF INDIAN AVE. & MARIPOSA AVE.
MV5	Moreno Valley Industrial Park	Moreno Valley	High-Cube Warehouse	207.684	TSF	NEC OF HEACOCK ST. & IRIS AVE.
MV6	Moreno Valley Walmart	Moreno Valley	Retail	193.000	TSF	SWC OF PERRIS BLVD. & GENTIAN AVE.
MV7	Moreno Valley Utility Substation	Moreno Valley	High-Cube Warehouse	PUBLIC	TSF	NWC OF EDWIN RD. & KITCHING ST.
MV8	Phelan Development	Moreno Valley	High-Cube Warehouse	98.210	TSF	SEC OF INDIAN ST. & NANDINA AVE.
MV9	Nandina Industrial Center	Moreno Valley	High-Cube Warehouse	335.966	TSF	SOUTH OF NANDINA AVE. WEST OF PERRIS BLVD.
MV10	MV10 Indian Street Commerce Center	Moreno Valley	High-Cube Warehouse	433.918	TSF	SWC OF INDIAN ST. & GROVEVIEW RD.
MV11	MV11 Tract 22180	Moreno Valley	SFDR	140	DO	NORTH OF GENTIAN AVE. EAST OF INDIAN ST.
MV12	MV12 Tract 36760	Moreno Valley	SFDR	221	DO	SEC OF INDIAN ST. & GENTIAN AVE.
MV13	MV13 PEN18-0042	Moreno Valley	SFDR	2	DO	SEC OF INDIAN ST. & KRAMERIA AVE.
MV14	MV14 Tract 33024	Moreno Valley	SFDR	8	DO	SEC OF INDIAN ST. & KRAMERIA AVE.
MV15	MV15 Tract 32716	Moreno Valley	SFDR	57	DO	NEC OF INDIAN ST. & MARIPOSA AVE.
MV16	MV16 Tract 31442	Moreno Valley	SFDR	63	DO	NWC OF PERRIS BLVD. & MARIPOSA AVE.
RC1	RC1 McCanna Hills / TTM 33978	County of Riverside	SFDR	63	DO	SWC OF SHERMAN AVE. & WALNUT AVE.

¹ SFDR = Single Family Detached Residential
² DU = Dwelling Units; TSF = Thousand Square Feet

4.8 NEAR-TERM TRAFFIC CONDITIONS

The "buildup" approach combines existing traffic counts with a background ambient growth factor to forecast EA (2020), EAP (2020), EAC (2020), and EAPC (2020) traffic conditions. An ambient growth factor of 6.09% to account for background (area-wide) traffic increases that occur over time up to the year 2020 from the year 2018 (compounded 3.0 percent per year growth over a 2-year period). Traffic volumes generated by the Project are then added to assess the near-term traffic conditions. The 2020 roadway networks are similar to the Existing conditions roadway network, with the exception of future driveways proposed to be developed by the Project.

The near-term traffic analysis includes the following traffic conditions, with the various traffic components:

- Existing Plus Ambient Growth (2020)
 - o Existing 2018 counts
 - Ambient growth traffic (6.09%)
- Existing Plus Ambient Growth plus Project (2020)
 - o Existing 2018 counts
 - Ambient growth traffic (6.09%)
 - Project traffic
- Existing Plus Ambient Growth Plus Cumulative (2020)
 - o Existing 2018 counts
 - Ambient growth traffic (6.09%)
 - Cumulative Development traffic
- Existing Plus Ambient Growth Plus Cumulative Plus Project (2020)
 - Existing 2018 counts
 - Ambient growth traffic (6.09%)
 - Cumulative Development traffic
 - Project traffic



5 E+P TRAFFIC CONDITIONS

This section discusses the traffic forecasts for Existing Plus Project (E+P) conditions and the resulting intersection operations and traffic signal warrant analyses.

5.1 ROADWAY IMPROVEMENTS

The lane configurations and traffic controls assumed to be in place for E+P conditions are consistent with those shown previously on Exhibit 3-1, with the exception of the following:

Project driveways and those facilities assumed to be constructed by the Project to provide site
access are also assumed to be in place for E+P conditions only (e.g., intersection and roadway
improvements at the Project's frontage and driveways). This includes the Project aligning its
Driveway 2 with the existing Perry Street to create a 4-leg, full access intersection.

5.2 E+P Traffic Volume Forecasts

This scenario includes Existing traffic volumes plus Project traffic. Exhibit 5-1 shows the ADT and peak hour intersection turning movement volumes (in PCE), which can be expected for E+P traffic conditions.

5.3 Intersection Operations Analysis

E+P peak hour traffic operations have been evaluated for the study area intersections based on the analysis methodologies presented in Section 2 *Methodologies* of this TIA. The intersection analysis results are summarized in Table 5-1, which indicate that the study area intersections are anticipated to continue to operate at an acceptable LOS during the peak hours, consistent with Existing (2018) traffic conditions.

Exhibit 5-2 summarizes the weekday AM and PM peak hour study area intersection LOS under E+P traffic conditions, consistent with the summary provided in Table 5-1. The intersection operations analysis worksheets are included in Appendix 5.1 of this TIA.

5.4 TRAFFIC SIGNAL WARRANTS ANALYSIS

There are no study area intersections anticipated to meet peak hour volume-based traffic signal warrants under E+P traffic conditions (see Appendix 5.2).



0.2 PERRY ST. 2 0.5 DWY. 2(T) (FULL) CEQA STUDY AREA DWY. 3 (P) (RIRO) 0.1 **DWY 1. (P)** INDIAN AV. (RIRO) 48.7 (\mathbf{I}) 48.7 RAMONA EXWY.

EXHIBIT 5-1: E+P TRAFFIC VOLUMES (IN PCE)

1 Dwy. 1 & Ramona Exwy.			Indian Av. & . 2 / Perry St.	3	Indian Av. & Dwy. 3		Indian Av. & Ramona Exwy.
4–4(19)	13(6) ←1502(1291)	←20(7) ←113(303) ←5(5)	4—3(6) ←0(0) ←5(5)	←5(3) ←108(300)		←38(59) ←52(182) ←20(65)	—98(53) —1383(1138) —63(118)
1176(1473)-		7(18)→ 0(0)→ 0(0)¬,	0(0) 354(249) - 20(5) -	1(5)—,	373(254)→	150(93)— 966(1286)— 60(94)—	86(96) 4 135(113) 7 44(30) 7

10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES 10.0 = VEHICLES PER DAY (1000'S)



PERRY ST. DWY. 2(T) CEQA STUDY AREA DWY. 3 (P) (RIRO) DWY 1. (P) **NDIAN AV.** (RIRO) RAMONA EXWY.

EXHIBIT 5-2: E+P SUMMARY OF LOS





Table 5-1

Intersection Analysis for E+P Conditions

			Existing (2018)							
			HCM Delay ¹ Le			el of	HCM	Delay ¹	Lev	el of
		Traffic	(se	Ser	vice	(secs.)		Service		
#	Intersection	Control ²	AM	AM	PM	AM	PM	AM	PM	
1	Driveway 1 & Ramona Expressway	<u>CSS</u>	Futi	ection		18.2	16.6	С	С	
2	Indian Avenue & Driveway 2/Perry Street	CSS	9.6	9.6 9.1 A			11.3	12.1	В	В
3	Indian Avenue & Driveway 3	<u>CSS</u>	Future Intersection			n	8.6	9.2	Α	Α
4	Indian Avenue & Ramona Expressway	TS	19.1	19.7	В	В	19.4	19.8	В	В

Per the Highway Capacity Manual (6th Edition), overall average intersection delay and level of service are shown for intersections with a traffic signal or all way stop control. For intersections with cross street stop control, the delay and level of service for the worst individual movement (or movements sharing a single lane) are shown.



² CSS = Cross-Street Stop; TS = Traffic Signal; <u>CSS</u> = Improvement

6 EA AND EAP (2020) TRAFFIC ANALYSIS

This section discusses the methods used to develop EA and EAP (2020) traffic forecasts, and the resulting intersection operations and traffic signal warrant analyses.

6.1 ROADWAY IMPROVEMENTS

The lane configurations and traffic controls assumed to be in place for EA and EAP (2020) conditions are consistent with those shown previously on Exhibit 3-1, with the exception of the following:

Project driveways and those facilities assumed to be constructed by the Project to provide site
access are also assumed to be in place for EAP conditions only (e.g., intersection and roadway
improvements at the Project's frontage and driveways). This includes the Project aligning its
Driveway 2 with the existing Perry Street to create a 4-leg, full access intersection.

6.2 EA (2020) TRAFFIC VOLUME FORECASTS

This scenario includes Existing (2018) traffic volumes plus an ambient growth factor of 6.09%. Exhibit 6-1 shows the weekday ADT and peak hour volumes which can be expected for EA (2020) traffic conditions.

6.3 EAP (2020) TRAFFIC VOLUME FORECASTS

This scenario includes Existing (2018) traffic volumes plus an ambient growth factor of 6.09% and the addition of Project traffic. Exhibit 6-2 shows the weekday ADT and peak hour volumes which can be expected for EAP (2020) traffic conditions (in PCE).

6.4 Intersection Operations Analysis

Level of service calculations were conducted for the study intersections to evaluate their operations under EA and EAP (2020) conditions with existing roadway and intersection geometrics consistent with those described under Section 6.1 *Roadway Improvements*. As shown in Table 6-1 and illustrated on Exhibits 6-3 and 6-4, there are no study area intersections that are anticipated to operate at an unacceptable LOS under both EA and EAP (2020) traffic conditions.

The intersection operations analysis worksheets for EA and EAP (2020) conditions are included in Appendices 6.1 and 6.2 of this report, respectively.

6.5 TRAFFIC SIGNAL WARRANTS ANALYSIS

No traffic signal warrant analysis has been performed for EA (2020) traffic conditions as the only unsignalized intersection is restricted to right-in/right-out access only. Traffic signal warrants have been performed (based on CA MUTCD) for EAP (2020) traffic conditions based on peak hour volumes. For EAP (2020) traffic conditions, no traffic signals are warranted (see Appendix 6.3).



SITE


*

DWY. 3 (P)

(RIRO)

AND MAIN INTERPRETATION OF THE PROPERTY ST.

EXHIBIT 6-1: EA (2020) TRAFFIC VOLUMES (IN PCE)



0

10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES

10.0 - VEHICLES PER DAY (1000'S)

RAMONA EXWY.

NOM = NOMINAL, LESS THAN 50 VEHICLES PER DAY



4

48.8

0.2 PERRY ST. 2 0.5 DWY. 2(T) (FULL) CEQA STUDY AREA DWY. 3 (P) (RIRO) 0.1 **DWY 1. (P)** INDIAN AV. (RIRO) 51.6 (\mathbf{I}) RAMONA EXWY.

EXHIBIT 6-2: EAP (2020) TRAFFIC VOLUMES (IN PCE)

1 Dwy. 1 & Ramona Exwy							
1247(1562)—	000 (1000) (1000) (1	50 ←5(3) 50 ←115(318) 396(269) →	103(56) -1467(1207) -66(125) 1025(1364) -64(100) -6				

10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES 10.0 = VEHICLES PER DAY (1000'S)



PERRY ST. SITE DWY. 3 (P) (NA) * (RIRO) **DWY 1. (P)** NDIAN AV. (RIRO) (NA) **LEGEND:** RAMONA EXWY. **- AM PEAK HOUR PM PEAK HOUR** - LOS A-D - LOS E - LOS F - NOT AN ANALYSIS LOCATION FOR THIS SCENARIO

EXHIBIT 6-3: EA (2020) SUMMARY OF LOS



PERRY ST. CEQA STUDY AREA DWY. 3 (P) (RIRO) DWY 1. (P) **NDIAN AV.** (RIRO) RAMONA EXWY.

EXHIBIT 6-4: EAP (2020) SUMMARY OF LOS





Intersection Analysis for EA (2020) and EAP (2020) Conditions

Table 6-1

			EA (2020)			EAP (2020)				
			HCM Delay ¹		Level of		HCM Delay ¹		Level of	
		Traffic	(secs.)		Service		(secs.)		Service	
1	Intersection	Control ²	AM	PM	AM	PM	AM	PM	AM	PM
1	Driveway 1 & Ramona Expressway	CSS	Future Intersection				19.2	17.4	С	С
2	Indian Avenue & Perry Street	CSS	9.7	9.2	Α	Α	11.5	12.3	В	В
3	Indian Avenue & Driveway 3	<u>CSS</u>	Future Intersection			n	8.6	9.3	Α	Α
4	Indian Avenue & Ramona Expressway	TS	19.8	18.4	В	В	20.2	20.5	С	С

Per the Highway Capacity Manual (6th Edition), overall average intersection delay and level of service are shown for intersections with a traffic signal or all way stop control. For intersections with cross street stop control, the delay and level of service for the worst individual movement (or movements sharing a single lane) are shown.



² CSS = Cross-Street Stop; TS = Traffic Signal; $\underline{\textbf{CSS}}$ = Improvement

7 EAC AND EAPC (2020) TRAFFIC CONDITIONS

This section discusses the methods used to develop EAC and EAPC (2020) traffic forecasts and the resulting intersection operations and traffic signal warrant analyses.

7.1 ROADWAY IMPROVEMENTS

The lane configurations and traffic controls assumed to be in place for EAC and EAPC (2020) conditions are consistent with those shown previously on Exhibit 3-1, with the exception of the following:

Project driveways and those facilities assumed to be constructed by the Project to provide site
access are also assumed to be in place for EAPC conditions only (e.g., intersection and roadway
improvements along the Project's frontage and driveways). This includes the Project aligning its
Driveway 2 with the existing Perry Street to create a 4-leg, full access intersection.

7.2 EAC (2020) TRAFFIC VOLUME FORECASTS

To account for background traffic, other known cumulative development projects in the study area were included in addition to 6.09% of ambient growth for EAC (2020) traffic conditions. The weekday ADT and weekday AM and PM peak hour volumes (in PCE) which can be expected for EAC (2020) Without Project traffic conditions are shown on Exhibit 7-1.

7.3 EAPC (2020) TRAFFIC VOLUME FORECASTS

To account for background traffic, other known cumulative development projects in the study area were included in addition to 6.09% of ambient growth for EAPC (2020) traffic conditions in conjunction with traffic associated with the proposed Project. The weekday ADT and weekday AM and PM peak hour volumes (in PCE) which can be expected for EAPC (2020) With Project traffic conditions are shown on Exhibit 7-2.

7.4 Intersection Operations Analysis


LOS calculations were conducted for the study intersections to evaluate their operations under EAC (2020) conditions with roadway and intersection geometrics consistent with Section 7.1 *Roadway Improvements*. As shown in Table 7-1, all the study area intersections are anticipated to operate at acceptable LOS during the peak hours under EAC (2020) and EAPC (2020) traffic conditions.

A summary of the peak hour intersection LOS for EAC (2020) conditions are shown on Exhibit 7-3 and on Exhibit 7-4 for EAPC (2020) traffic conditions. The intersection operations analysis worksheets for EAC and EAPC (2020) traffic conditions are included in Appendix 7.1 and Appendix 7.2 of this TIA, respectively.



EXHIBIT 7-1: EAC (2020) TRAFFIC VOLUMES (IN PCE)





10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES

10.0 - VEHICLES PER DAY (1000'S)

NOM = NOMINAL, LESS THAN 50 VEHICLES PER DAY



0.2 PERRY ST. 2 0.5 DWY. 2(T) (FULL) CEQA STUDY AREA DWY. 3 (P) (RIRO) 0.1 **DWY 1. (P)** INDIAN AV. (RIRO) 60.5 (\mathbf{I}) 60.4 RAMONA EXWY.

EXHIBIT 7-2: EAPC (2020) TRAFFIC VOLUMES (IN PCE)

1 Dwy. 1 & Ramona Exwy.		3 Indian Av. & Dwy. 3					
(a) 13(6) → 13(6) → 1986(1709) 1542(2126)→	000 (000) (100	603(794) +	310(401) - 153(156) -1749(1382) -66(125) 310(401) - 16(125) 310(401) - 16(125) 31				

10(10) = AM(PM) PEAK HOUR INTERSECTION VOLUMES 10.0 = VEHICLES PER DAY (1000'S)



PERRY ST. SITE DWY. 3 (P) (NA) * (RIRO) **DWY 1. (P)** NDIAN AV. (RIRO) (NA) **LEGEND:** RAMONA EXWY. - AM PEAK HOUR

EXHIBIT 7-3: EAC (2020) SUMMARY OF LOS



PM PEAK HOUR

- NOT AN ANALYSIS LOCATION FOR THIS SCENARIO

LOS A-DLOS ELOS F

PERRY ST. CEQA STUDY AREA DWY. 3 (P) (RIRO) DWY 1. (P) **NDIAN AV.** (RIRO) RAMONA EXWY.

EXHIBIT 7-4: EAPC (2020) SUMMARY OF LOS





Intersection Analysis for EAC (2020) and EAPC (2020) Conditions

Table 7-1

			EA (2020)				EAPC (2020)			
			HCM Delay ¹		Level of		HCM Delay ¹		Level of	
		Traffic	(secs.)		Service		(secs.)		Service	
#	Intersection	Control ³	AM	PM	AM	PM	AM	PM	AM	PM
1	Driveway 1 & Ramona Expressway	<u>CSS</u>	Future Intersectio			1	24.8	21.9	С	С
2	Indian Avenue & Perry Street	CSS	10.6	11.5	В	В	14.1	17.9	В	С
3	Indian Avenue & Driveway 3	<u>CSS</u>	Future Intersection			1	9.2	10.2	Α	В
4	Indian Avenue & Ramona Expressway	TS	33.1 42.5		С	D	34.6	53.7	С	D

Per the Highway Capacity Manual (6th Edition), overall average intersection delay and level of service are shown for intersections with a traffic signal or all way stop control. For intersections with cross street stop control, the delay and level of service for the worst individual movement (or movements sharing a single lane) are shown.



² CSS = Cross-Street Stop; TS = Traffic Signal; <u>CSS</u> = Improvement

7.5 TRAFFIC SIGNAL WARRANTS ANALYSIS

No traffic signal warrant analysis has been performed for EAC (2020) traffic conditions as the only unsignalized intersection is restricted to right-in/right-out access only. Traffic signal warrants have been performed (based on CA MUTCD) for EAPC (2020) traffic conditions based on peak hour volumes. For EAPC (2020) traffic conditions, no traffic signals are warranted (see Appendix 7.3).

7.6 SUMMARY OF FINDINGS

All the study area intersections operate at acceptable LOS for all the scenarios. Therefore, there are no direct Project impacts. Each project implementing the PVCC SP is required to incorporate applicable mitigation from the PVCC Specific Plan EIR. The relevant traffic mitigation measures from the PVCC Specific Plan EIR were previously identified in Section 1.4.1.

In addition, Project truck traffic shall be restricted to take Harley Knox Boulevard as the one and only truck route to access the I-215 Freeway. Signage shall be posted on-site directing truck drivers to use the existing City truck route on Harley Knox Boulevard. The information on the signage will be coordinated with City Planning and the City's traffic Engineering during the plan check process.



This Page Intentionally Left Blank



8 REFERENCES

- 1. **Institute of Transportation Engineers.** *Trip Generation.* 10th Edition. 2017.
- 2. **Riverside County Transportation Commission.** 2011 Riverside County Congestion Management *Program.* County of Riverside: RCTC, December 14, 2011.
- 3. American Association of State Highway and Transportation Officials. *Geometric Design of Highways and Streets*. 2004.
- 4. **California Department of Transportation.** *Guide for the Preparation of Traffic Impact Studies.* December 2002.
- 5. **Transportation Research Board.** *Highway Capacity Manual (HCM).* s.l. : National Academy of Sciences, 2010.
- Federal Highway Administration. California Manual on Uniform Traffic Control Devices (MUTCD). [book auth.] California Department of Transportation. California Manual on Uniform Traffic Control Devices (CAMUTCD). 2017.
- 7. City of Perris. General Plan Circulation Element. City of Perris: s.n., August 26, 2008.
- 8. San Bernardino Associated Governments. Congestion Management Program for County of San Bernardino. County of San Bernardino: s.n., Updated 2016.
- 9. **Institute of Transportation Engineers.** *High Cube Warehouse Vehicle Trip Generation Analysis.* Washington, DC: Institute of Transportation Engineers, October 2016.
- 10. **Southern California Association of Governments.** *2012-2040 Regional Transportation Plan.* April 2016.



This Page Intentionally Left Blank

